



EXISTING WALLS
 NEW WALLS

NOTE:
 (1) JACK AT EACH SIDE OF EACH DOOR/WINDOW HEADER,
 UNLESS OTHERWISE NOTED

FASTENER SCHEDULE	
SILL PLATE TO FOUNDATION	1/2" ANCHOR BOLT @ 36" O.C. W/ 3" PLATE WASHER; 9" MIN. EMBEDMENT
ROOF SHEATHING	8d @ 6" O.C. EDGE / 12" O.C. FIELD (TYPICAL PANELS) 8d @ 6" O.C. EDGE / 6" O.C. FIELD (PERIMETER PANELS)
WALL SHEATHING	8d @ 6" O.C. EDGE / 12" O.C. FIELD
FLOOR SHEATHING	12d RING OR SPIRAL NAILS @ 6" O.C. EDGE / 12" O.C. FIELD
POST BASES TO CONCRETE	SIMPSON TYPE AB
POST CAPS	SIMPSON BC OR LC (MATCH POST SIZE)
JOIST ON SILL, TOP PLATE, OR ORDER	SIMPSON LUS HANGER OR 4 - 8d (TOENailed) WHEN JOIST BEARS ON SUPPORT
BRIDGING / BLOCKING TO JOIST	2 - 8d (TOENailed)
BLOCKING TO SILL / TOP PLATE	3 - 16d (TOENailed)
LEDGER STRIP TO BEAM	3 - 16d (FACENailed, PER JOIST)
JOIST ON LEDGER TO BEAM	3 - 8d (TOENailed)
BAND / RIM JOIST TO JOIST	3 - 16d (ENDNailed)
RIM JOIST TO SILL / TOP PLATE	2 - 16d PER FOOT
TOP PLATE TO TOP PLATE	2 - 16d PER FOOT
TOP PLATES AT INTERSECTION	4 - 16d EACH SIDE
STUD TO STUD	1 - 16d @ 12" O.C.
HEADER TO HEADER	16d @ 8" O.C. ALONG EDGES
TOP OR BOTTOM PLATE TO STUD	2 - 16d
BOTTOM PLATE TO JOIST OR BLOCKING	2 - 16d PER FOOT
RAFTER TO TOP PLATE	SIMPSON H1 HURRICANE TIE
CEILING JOIST TO TOP PLATE	2 - 8d (TOENailed)
BLOCKING TO RAFTER	2 - 8d EACH END
BAND JOIST TO RAFTER	2 - 16d EACH END
SLOPED/SKEWED RAFTER HANGERS AT RIDGE/HP BEAMS	SIMPSON LSU

DATE	NOTES
2015.09.17	
REVISION	

1/4"=1'

Medlen Residence
 34 Sterling St.
 Peaks Island, ME

PROJECT

A Proposed Roof Framing Plan



S3
 Proposed
 Roof Framing
 Plan

Rachel Conly
 Architectural Design
 26 Sterling Street
 Peaks Island, Maine 04108
 207.766.5625