HVAC DEMOLITION - 1ST FLOOR PLAN

SCALE: 1/4"=1'-0"

DEMOLITION NOTES

1. CUT IN-SLAB PIPING FLUSH WITH SURFACE, GROUT AND FINISH TO MATCH FINISH FLOORING.
2. REMOVE EXISTING CABINET UNIT HEATER, FINTUBE AND ENCLOSURE
3. REMOVE PIPING
4. REMOVE THERMOSTAT, PATCH WALL TO MATCH ADJACENT WALL FINISH.
5. EXISTING TO REMAIN
6. REMOVE EXISTING TOILET EXHAUST SYSTEM

HVAC DEMOLITION - MEZZANINE PLAN

SCALE: 1/4"=1'-0"

12-21-16 Issued for Review

4-12-17 Issued for Bidding

STATE OF MAINE
ANDREW W. HOLBROOK
No. 9103
4/12/2017
LICENSED
PROFESSIONAL ENGINEER

Date: 04/25/17

ARCHITECT:

REED & CO. ARCHITECTURE
46 CUMBERLAND AVE
PORTLAND, ME 04101
207 871 5678

INTERIOR DESIGNER:

COLE DESIGN
PO BOX 361
KITTERY, ME 03904
207 653 0083

STRUCTURAL ENGINEER

SHELLEY ENGINEERING
PO BOX 1030
GRAY, ME 04039
207 657 8031

MECHANICAL ENGINEER:

HOLBROOK ENGINEERING
52 HEATH RD
SACO, ME 04072
207 283 9127

ELECTRICAL ENGINEER:

BARTLETT DESIGN
942 WASHINGTON STREET
BATH, MAINE 04530
207 443 5447

PROPOSED IMPROVEMENTS

PEAKS ISLAND COMMUNITY CENTER & LIBRARY

Title:
HVAC DEMOLITION PLAN

Sheet No.
M1.1

Scale: 1/4" = 1'-0"

Date:

Revised: