HVAC NEW - 1ST FLOOR PLAN

SCALE: 1/4"=1'-0"

HVAC NEW - MEZZANINE PLAN

SCALE: 1/4"=1'-0"

NEW WORK NOTES

1. RUN HYDRONIC PIPING IN VOID UNDER SHELVING
2. REFRIGERANT PIPING RUN IN CEILING SPACE. INSULATE VAPOR AND LIQUID LINE WITH 1/2" ELASTOMERIC INSULATION RATED FOR 215°F SERVICE.
3. PROVIDE NEW ENDCAPS FOR RELOCATED FINTUBE ENCLOUSRES. MATCH EXISTING ENCLOSURE STYLE..
4. RUN DROPS IN NEW FIRRED OUT WALL. DO NOT INSTALL BUILDING ENVELOPE INSULATION IN STUD SPACE WHERE HYDRONIC PIPING IS LOCATED.
5. RUN IN CEILING SPACE, BELOW INSULATION.

12-21-16 Issued for Review

4-12-17 Issued for Bidding

STATE OF MAINE
ANDREW W. HOLBROOK
No. 9103
4/12/2017
LICENSED
PROFESSIONAL ENGINEER

Date: 04/25/17

ARCHITECT:

REED & CO. ARCHITECTURE
46 CUMBERLAND AVE
PORTLAND, ME 04101
207 871 5678

INTERIOR DESIGNER:

COLE DESIGN
PO BOX 361
KITTERY, ME 03904
207 653 0083

STRUCTURAL ENGINEER

SHELLEY ENGINEERING
PO BOX 1030
GRAY, ME 04039
207 657 8031

MECHANICAL ENGINEER:

HOLBROOK ENGINEERING
52 HEATH RD
SACO, ME 04072
207 283 9127

ELECTRICAL ENGINEER:

BARTLETT DESIGN
942 WASHINGTON STREET
BATH, MAINE 04530
207 443 5447

PROPOSED IMPROVEMENTS

PEAKS ISLAND COMMUNITY CENTER & LIBRARY

Title:
HVAC PLAN

Sheet No.
M2.0

Scale: 1/4" = 1'-0"

Date:

Revised: