MEZZANINE DEMOLITION PLAN

FIRST FLOOR DEMOLITION PLAN

GENERAL NOTES

1. COORDINATE REVOVAL OF ELECTRICAL AND MECHANICAL ITEMS WITH MECHANICAL AND ELECTRICAL CONTRACTORS.
2. REMOVE ALL EXISTING CONSTRUCTION AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION, MATERIALS AND EQUIPMENT.
3. CEILINGS
   REMOVE ALL EXISTING CEILINGS, INCLUDING HANGARS, TRACKS, AND STRAPPING.
   REMOVE FIBERGLASS BATT INSULATION.
4. FLOORING
   CARPET: REMOVE ALL EXISTING CARPET, INCLUDING ADHESIVE
   VCT: REMOVE ALL EXISTING VCT, INCLUDING ADHESIVE
   UNLESS NOTED "TO REMAIN"

DEMOLITION LEGEND

EXISTING WALL TO REMAIN

EXISTING WALL TO BE REMOVED

EXISTING WINDOW TO BE REMOVED

EXISTING DOOR & FRAME TO BE REMOVED

EXISTING CONCRETE FLOOR SLAB TO BE REMOVED

0 2' 4' 8'

12-21-16 Issued for Review
4-12-17 Issued for Bidding

REGISTERED ARCHITECT
RICHARD A. REED
No. 1202
STATE OF MAINE

Date: 04/25/17

ARCHITECT:
REED & CO. ARCHITECTURE
46 CUMBERLAND AVE
PORTLAND, ME 04101
207 871 5678

INTERIOR DESIGNER:
COLE DESIGN
PO BOX 361
KITTERY, ME 03904
207 653 0083

STRUCTURAL ENGINEER
SHELLEY ENGINEERING
PO BOX 1030
GRAY, ME 04039
207 657 8031

MECHANICAL ENGINEER:
HOLBROOK ENGINEERING
52 HEATH RD
SACO, ME 04072
207 283 9127

ELECTRICAL ENGINEER:
BARTLETT DESIGN
942 WASHINGTON STREET
BATH, MAINE 04530
207 443 5447

PROPOSED IMPROVEMENTS

PEAKS ISLAND COMMUNITY CENTER & LIBRARY

Title:
DEMOLITION PLANS

Sheet No.
A1.0

Scale: 1/4" = 1'-0"
Date:
Revised: