



Dewberry Engineers Inc. | 617.695.3400
280 Summer Street, 10th Floor | 617.695.3310 fax
Boston, MA 02210 | www.dewberry.com

November 28, 2016

Mr. Dan Myzyri
Structure Consulting Group
49 Brattle Street
Arlington, MA 02474

**Re: Portland 6 ME
125 Church Ave.
Peaks Island, ME 04108**

Dear Mr. Myzyri,

Verizon Wireless has proposed to replace (3) existing RRH2X40-AWS (44 lbs.) remote radio heads with (3) new B66A RRH 4X45 (66 lbs.) remote radio heads inside the steeple at the above referenced site. The new RRH's will utilize the existing unistrut inside the church steeple.

Dewberry has evaluated the proposed configuration and has determined that the existing steeple structure has adequate reserve capacity to support the proposed conditions. The proposed installation is outlined in associated ANTMO Drawings by Dewberry Engineers Inc. (Dewberry) dated July 19th, 2016.

Our assessment is based on the assumption that the existing structure is in good condition and was constructed in conformance with all applicable state and local building codes. If during construction any damage or deterioration is noticed, Dewberry is to be notified to assess any deviation from the assumed condition. The addition of any new equipment not accounted for on the plans will require further analysis and design.

If you have any questions, please do not hesitate to call me at 617-531-0742.

Sincerely,
Dewberry Engineers Inc.

Brenden Alexander, P.E.
Senior Project Manager

