NOTES

	DUPLEX RECEPTACLE		CEILING MOUNT LIGHT FIXTURE		UNDER-COUNTER LIGHTS		PHONE JACK
GFI	GROUND FAULT CIRCUIT INTERUPTER		PENDANT LIGHT FIXTURE		TRACK LIGHTING	DSL	DSL JACK
240	240 V	RC	RECESSED CAN LIGHT FIXTURE		LOCALLY SWITCHED CLOSET RATED LIGHT	C	CABLE JACK
$	SWITCH		WALL SCONCE LIGHT FIXTURE	$	CEILING FAN WITH INTEGRAL LIGHT	C5	CAT 5 JACK
3 $	3-WAY SWITCH	WL	WET LOCATION WALL SCONCE LIGHT FIXTURE			CV	CENTRAL VACUUM PORT
D $	DIMMER SWITCH	FC	COMPACT FLUORESCENT RECESSED CAN LIGHT		CEILING FAN		
SD	SMOKE DETECTOR	LED	LED RECESSED CAN LIGHT		MINIMUM 50 CFM VENT FAN		
CO	CARBON MONOXIDE DETECTOR						

ELECTRICAL, PLUMBING, AND MECHANICAL PERMITS BY OTHERS

CONTRACTOR TO PROVIDE SEPARATE PRICING TO MOVE ELECTRICAL PANEL FROM CRAWLSPACE INTO LIVING SPACE (CONSIDER DINING ROOM AND ATTIC AS POSSIBLE LOCATIONS)

NOTE: CONTRACTOR TO PURCHASE, DELIVER, AND INSTALL ALL PROJECT MATERIALS, COMPONENTS, FINISHES, APPLICANCES AND FIXTURES, UNLESS OTHERWISE NOTED, AND IS FULLY RESPONSIBLE FOR TIMELY AND LEGAL DISPOSAL OF ALL PROJECT RELATED WASTE. PROVIDE STATED ALLOWANCES IN ESTIMATE/QUOTE FOR ITEMS TO BE SELECTED BY CLIENT.

EXISTING WALL

NEW WALL

A Proposed First Power Plan

ELECTRICAL, PLUMBING, AND MECHANICAL PERMITS BY OTHERS

NOTE: CONTRACTOR TO PURCHASE, DELIVER, AND INSTALL ALL PROJECT MATERIALS, COMPONENTS, FINISHES, APPLICANCES AND FIXTURES, UNLESS OTHERWISE NOTED, AND IS FULLY RESPONSIBLE FOR TIMELY AND LEGAL DISPOSAL OF ALL PROJECT RELATED WASTE. PROVIDE STATED ALLOWANCES IN ESTIMATE/QUOTE FOR ITEMS TO BE SELECTED BY CLIENT.

EXISTING WALL

NEW WALL

B Proposed First Floor Lighting Plan

STATE OF MAINE
ANDREW M. JACKSON
No. 13082
LICENSED
PROFESSIONAL ENGINEER

Inspections Division
Date: 10/29/15

Rachel Conly
Architectural Design
26 Sterling Street
Peaks Island, Maine 04108
207.766.5625

DATE	NOTES
2015.10.14	
REVISED	

1/4" = 1'

PROJECT
Gray Residence
13 City Point Rd.
Peaks Island, ME
04108

E1

Proposed First Floor Power & Lighting Plans