

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT

**This is to certify that**

SHIVER STEPHEN A & MARTHE C SHIVER JTS

**Located at**

71 CENTRAL AVE (Peaks Island)

**PERMIT ID:** 2015-01488

**ISSUE DATE:** 07/07/2015

**CBL:** 087 GG003001

has permission to **Remove existing rear steps. Replace with new landing and stairs. Add new wood decking on upper deck and ballusters and replace the EPDM.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
--	--

N/A

/s/ Laurie Leader

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*  
Single family

*Building Inspections*

*Fire Department*

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703 (ONLY)  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status or Schedule an Inspection On-Line at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

## **REQUIRED INSPECTIONS:**

Setbacks and Footings Prior to Pouring  
Foundation/Backfill  
Close-in Plumbing/Framing  
Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2015-01488	<b>Date Applied For:</b> 06/23/2015	<b>CBL:</b> 087 GG003001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Same: Single-Family Home		<b>Proposed Project Description:</b> Remove existing rear steps. Replace with new landing and stairs. Add new wood decking on upper deck and ballusters and replace the EPDM.		
<b>Dept:</b> Zoning		<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> Ann Machado	<b>Approval Date:</b> 07/01/2015
<b>Note:</b> Existing rear stairs did not meet building code and were nonconforming to setbacks. New landings and stairs are the minimum to meet code and the majority of the new footprint is within the footprint of the existing stairs. Using section 14-425 for the additional 44 sf. the landing extends 7' 8" instead of 6' but that is the minimum to meet code.		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Conditions:</b>				
1) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
<b>Dept:</b> Building Inspection		<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> Laurie Leader	<b>Approval Date:</b> 07/06/2015
<b>Note:</b>		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Conditions:</b>				
1) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
2) When over 30" above a floor or grade, guardrail openings shall be less than 4", stairail openings shall be less than 4-3/8", and at the open side of a stair, less than 6" is allowed at the triangle of the tread/riser at the bottom rail.				
3) Where supported by attachment to an exterior wall, decks shall be positively anchored to the primary structure and designed for both vertical and lateral loads as applicable. Such attachment shall not be accomplished by the use of toenails or nails subject to withdrawal. See IRC 2009 Sec. 502.2.2 and IBC Sec. 1604.8.3 for details.				
Deck lateral load connection shall be allowed with hold-down tension devices installed in not less than two locations per deck, with each device having an allowable stress design capacity of not less than 1500 pounds.				
Where positive connection to the primary building structure cannot be verified during inspection, decks shall be self- supporting.				
.				
4) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				