

# **Roof Mounting System**



The IronRidge (rail based) Roof Mount System is a reliable, comprehensive and feature rich photovoltaic mounting solution. Anchored by IronRidge Standard or IronRidge Light rails, our Roof Mount platform includes every component necessary for supporting virtually any commercial or residential roof mount installation, regardless of roof type or pitch. With this system, you will leave behind a professional installation, everytime, backed by a 20 year manufacturing warranty on every IronRidge part.





Maximum Span	IronRidge Standard Rail							IronRidge Light Rail					
Wind Speed	Snow 0 psf	Loads 10 psf	20 psf	30 psf	40 psf	50 psf	60 psf	70 psf	0 psf	10 psf	20 psf	30 psf	40 psf
90 mph	147"	123″	103″	94"	83″	75″	69"	64"	88″	75″	63″	59″	52″
100 mph	147"	123"	103"	94"	83″	75″	69"	64"	88″	75″	63″	59"	52″
110 mph	147"	123″	103″	94"	83″	75″	69"	64"	88″	75″	63″	59"	52″
120 mph	147"	123"	103"	94″	83″	75″	69"	64"	88″	75″	63″	59″	52″
130 mph	138"	123″	103"	94"	83″	75″	69"	64"	81″	75″	63″	59"	52″
140 mph	129"	120"	101″	94"	83″	75″	69"	64"	75"	73″	62″	58″	52"
150 mph	120"	117"	99"	93″	83″	75″	69"	64"	70″	70″	61″	57"	52″

Roof Zone 1, Flush Mount Only Roof slope = 7 to 27 deg. Exposure category B Module length = 67.5" Building mean roof height = 30' Clearance between roof and rail: 2" End Cant Span: 0.40 x adjacent interior span No rail splices in end spans. No rail splices in middle 1/3 of interior span. Single simple span(s). Tabulated values may be increased for multiple continuous spans.\*

\*For more information visit ironridge.com to download certification letters, installation guides, and use our Design Assistant software.

## Attachments

- · Adjustable L feet (4 pack kits)
- Adjustable tilt leg kits (5° to 45°)
- Flush mount aluminum standoffs (3", 4", 6", 7")
- Tilt mount aluminum standoffs (3.75", 7", 9")

## **End Caps**

Protect against debris while providing a finished look for both standard and light rails

## Why IronRidge?



**Experience** - Designing/manufacturing solar mounting products since 1996

**Single Source** - Roof mounts, ballasted mounts, ground and pole mounts; *a solution for your specific application* 

**Customer Satisfaction** - Customer service and technical support to help you succeed

## Clamps

- Panel Sizes 1.22" to 2.30"
- Mid clamps (require only 1/4" between panels)
- Mid clamps available in hex or t-bolt
- · All hardware stainless steel

## Wire Clips

Accommodate up to eight 6mm panel wires or an Enphase wire harness





On-line Resources Available:

- Online Design Assistant™
- · 360 Interactive Environments
- · Engineering Design Guides
- Product Certifications
- Installation Guides
- · Reseller Locator

Sales: 800-227-9523 sales@ironridge.com

www.IronRidge.com 1435 Baechtel Road Willits, CA 95490