

Albert Frick Associates, Inc
Environmental Consultants

95A County Road Gorham, Maine 04038
(207) 839-5563 FAX (207) 839-5564
www.albertfrick.com info@albertfrick.com

Albert Frick, SS, SE
James Logan, SS, SE
Matthew Logan, SE
Brady Frick, SE
Bryan Jordan, SE
William O'Connor, SE
Noel Dunn, Office Manager

June 18, 2015

Jesse Mantsch
101 Luther Street
Peaks Island, Maine 04108

Re: Preliminary Soil Evaluation, N/F Walsh Property (Map 88,C,Lots 7,8 & 9), 234 Park Avenue, Peaks Island

Dear Mr. Mantsch:

We visited the above referenced property on June 3, 2015. The purpose of the site visit was to determine the potential for onsite wastewater disposal. Attached is the preliminary site plan with the test pit locations and soil conditions observed.


The soils in the vicinity of Test Pit # 1 were found to be suitable, per the State of Maine, Subsurface Wastewater Disposal Rules. The soil is classified as 2 AIII, with bedrock encountered at 26". A typical 3 bedroom dwelling would require a 1000 gallon septic tank along with a 15' x 20' Eljen GSF disposal field or equivalent.

A completed Subsurface Wastewater Disposal System Design (HHE-200 Form) in order to obtain the necessary building permit to install the system. Please contact me if you have any questions or would like to have the design completed.

Respectfully,

Albert Frick

ML/ml



SOIL DESCRIPTION AND CLASSIFICATION (Location of Observation Holes Shown Above)

Observation Hole TP I Test Pit Boring
 " Depth of Organic Horizon Above Mineral Soil

	Texture	Consistency	Color	Mottling
0			DARK BROWN	
10	FINE SANDY LOAM	FRIABLE	YELLOWISH BROWN	
20				
30	REFUSAL LARGE STONES / BEDROCK			
40				
50				

Soil Classification 2 Profile AIII Condition
 Slope 5-8% Limiting Factor 26"

Ground Water
 Restrictive Layer
 Bedrock
 Pit Depth

Observation Hole TB A-D Test Pit Boring
 " Depth of Organic Horizon Above Mineral Soil

	Texture	Consistency	Color	Mottling
0				
10				
20				
30				
40				
50				

Soil Classification _____ Slope _____ % Limiting Factor _____

Ground Water
 Restrictive Layer
 Bedrock
 Pit Depth

Albert Frick
 Site Evaluator Signature

163
 SE *

6/18/15
 Date

Fill Estimation Worksheet

Albert Frick Associates Inc.

95A County Road

Gorham, Me 04038


839-5563 FAX - 839-5564

E-Mail - Albert@albertfrick.Com

www.albertfrick.com

Town: PORTLAND, PEAKS ISLAND
 Project owner/applicant: JESSE MANTSCH
 234 PARK AVENUE-2 BEDROOM

This worksheet is being provided as a complimentary tool to assist in estimating the **approximate** amount of fill required to construct the proposed system. This worksheet does not substitute for a personal visit to the site for your own estimate. These calculations are intended to serve as a check to your work. Site features beyond the model (terrain) can vary to affect model projections.



Length (L)	<u>20.00 feet</u>
Width (W)	<u>11 feet</u>
Shoulder (S)	<u>5 feet</u>
<i>Depth of fill:</i>	
upper left (a)	<u>19 inches</u>
upper right (c)	<u>19 inches</u>
lower left (b)	<u>21 inches</u>
lower right (d)	<u>27 inches</u>
<i>Fill Extension:</i>	
left up (e)	<u>6 feet</u>
right up (f)	<u>6 feet</u>
left down (g)	<u>7 feet</u>
right down (h)	<u>9 feet</u>
upper left (i)	<u>6 feet</u>
lower left (j)	<u>6 feet</u>
upper right (k)	<u>7 feet</u>
lower right (l)	<u>9 feet</u>
Cost of fill per yard= \$	<u>0.00</u>

15 ELJEN GSF
UNITS

Body	42 cubic yards
Fill Down	9 cubic yards
Fill Up	6 cubic yards
Fill left	4 cubic yards
Fill right	6 cubic yards
Fill upleft	1 cubic yards
Fill upright	1 cubic yards
Fill downleft	1 cubic yards
Fill downright	2 cubic yards

SubTotal= 72 cubic yards

Shrinkage %= 15 %

Total Backfill 83 cubic yards

Adjusted cost of Total

Backfill=

\$ -

Fill Estimation Worksheet

Albert Frick Associates Inc.

95A County Road

Gorham, Me 04038


839-5563 FAX - 839-5564

E-Mail - Albert@albertfrick.Com

www.albertfrick.com

Town: PORTLAND, PEAKS ISLAND
 Project owner/applicant: JESSE MANTSCH
 234 PARK AVENUE-3 BEDROOM

This worksheet is being provided as a complimentary tool to assist in estimating the **approximate** amount of fill required to construct the proposed system. This worksheet does not substitute for a personal visit to the site for your own estimate. These calculations are intended to serve as a check to your work. Site features beyond the model (terrain) can vary to affect model projections.



Length (L)	<u>20.00 feet</u>
Width (W)	<u>15 feet</u>
Shoulder (S)	<u>5 feet</u>
<i>Depth of fill:</i>	
upper left (a)	<u>19 inches</u>
upper right (c)	<u>19 inches</u>
lower left (b)	<u>21 inches</u>
lower right (d)	<u>27 inches</u>
<i>Fill Extension:</i>	
left up (e)	<u>6 feet</u>
right up (f)	<u>6 feet</u>
left down (g)	<u>7 feet</u>
right down (h)	<u>9 feet</u>
upper left (i)	<u>6 feet</u>
lower left (j)	<u>6 feet</u>
upper right (k)	<u>7 feet</u>
lower right (l)	<u>9 feet</u>
Cost of fill per yard= \$	<u>0.00</u>

20 ELJEN GSF
 UNITS

Body	50 cubic yards
Fill Down	9 cubic yards
Fill Up	6 cubic yards
Fill left	5 cubic yards
Fill right	8 cubic yards
Fill upleft	1 cubic yards
Fill upright	1 cubic yards
Fill downleft	1 cubic yards
Fill downright	2 cubic yards

SubTotal=	83 cubic yards
Shrinkage %=	15 %
Total Backfill	95 cubic yards

Adjusted cost of Total Backfill= \$ -