

- A.) Ledge removal is not included.
- B.) If requested by the owner, LPA will procure the City of Portland permit on the owners' behalf. The cost of the permit will be added to the final bill. Estimated cost: \$ -
- C.) LPA will schedule and attend all required inspections.
- D.) Maine state sales tax is included in the lump sum cost of both the septic system and the pump station and will be paid by LPA.

Job #4 - FOUNDATION EXCAVATION & BACKFILL **Cost:** \$ -

Foundation excavation and backfill with on-site material for a 36'x26' full foundation.

Job #5 - INTERIOR DRAINAGE & CRUSHED STONE **Cost:** \$ -

Installing interior foundation drainage pipes, fabric, fittings, radon vent and 3/4" crushed stone to the sub-floor grade.

MATERIALS:
 4" SDR 35 perforated pipe, fittings and fabric.....
 21.0 c.y. 3/4" crushed stone @ \$57.00/per c.y.....

Maine Sales Tax.....

LABOR:
 4.0 hours LPA crew & equipment @ \$375.00/hour.....

Job #6 - EXTERIOR DRAINAGE TO DAYLIGHT

MATERIALS:
 4" SDR 35 perforated pipe, solid pipe, fittings, fabric and radon flow-check.....
 20.0 c.y. 3/4" crushed stone @ \$57.00/per c.y.....

Maine Sales Tax.....

LABOR:
 4.0 hours LPA crew & equipment @ \$375.00/hour.....

Job #7 - DRIVEWAY

LPA will install a gravel driveway measuring approximately 12' x 40' x 6" deep. The driveway will be constructed with 3/4" crushed road gravel and compacted.

MATERIALS:
 9.0 c.y. 3/4" crushed road gravel @ \$59.00/per c.y.....

Maine Sales Tax.....

LABOR:
 1.0 hours LPA crew & equipment @ \$375.00/hour.....

Job #8 - EROSION CONTROL MEASURES

MATERIALS:
 300.0 feet of silt fence.....
 1.5 c.y. sand @ \$47.00/per c.y.....

Maine Sales Tax.....