

**LABOR:**

1.0 hour LPA crew & equipment @ \$375.00/hour.....

**Job #9 – LOAMING, FINISH GRADING, SEEDING AND MULCHING AROUND THE NEW HOUSE**  
**Cost: \$6,519.59**

**MATERIALS:**

72.0 c.y. of screened loam @ \$51.00/c.y.....  
Scotts Grass Seed.....  
10.0 bales of hay@ \$15.00/bale.....\$

**Maine Sales Tax**.....

**LABOR:**

6.0 hours LPA crew & equipment @ \$375.00/hour.....

**Job #10 – INSTALLING DEEP WATER**  
**Cost:**

**MATERIALS:**

1" CTS Waterline.....  
1" CTS Stainless Steel Tube Stiffeners.....  
1" Pipe Insulation.....  
1" Curbstop Assembly.....  
1" Saddle Tapp.....  
1" Ball Corp.....  
7.0 c.y. of ¾" Crushed Road Gravel (for road repair) @ \$59.00/c.y.....  
18.0 c.y. of sand (to protect the water main and bed & protect the new waterline) @ \$47.00/c.y.....

**Maine Sales Tax**.....

**LABOR:**

1.5 days LPA crew & equipment @ \$3,000.00/day.....  
Portland Water District approved tapper to tap the water main on Central Ave .....

**Job #10 Notes:**

- A.) LPA will apply for the street opening permit on the owners' behalf. The cost of this permit will be added to the final bill. Permit is estimated to be:
- B.) All permits required by the Portland Water District will be the owners' responsibility. Any fees associated with the Portland Water District, including the tapp inspection are not included in this estimate.
- C.) The Portland Water District requires us to use an approved tapper to tap the water main. LPA pays this fee to the tapper and it is not marked up.
- D.) Ledge removal is not included.
- E.) Sales tax will be added to all taxable items upon final billing.

## General Bid Notes

- 1.) Ledge removal is not included. Each item assumes that ledge is not encountered. Should we encounter ledge we would revisit the pricing and best options in a meeting with LPA Inc and the homeowner. The project would continue after the signing of a change order. LPA Inc recommends discussing ledge removal estimates prior to signing.
- 2.) All barge transportation relating to this estimate is included as noted.
- 3.) Pricing is contingent upon all job estimates being completed as a single project.
- 4.) Maine sales tax will be added to all taxable items upon final billing.