BIM Server: server.kaplanthompson.com - BIM Server 19/STZ-CD

	KTA Window & I			Tu :: :::05=	lus veez	lo	l a	laa	Tager 1.1	T -	To: :	louce	Liver	T=: ·	INT
D	Elevation	Width	Height	Units HORZ	Units VERI	Quantity	Area	Manufacturer	Material	Туре	Glazing	SHGC	U-Value	Tempered	Notes
1		2'-0"	5'-0"			1	10.68	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13		Egress
2		2'-0"	5'-0"			1	10.68	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13		
3		2'-0"	5'-0"			1	10.68	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13	YES	
4		2'-0"	5'-0"			1	10.68	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13		
5		2'-0"	5'-0"			1	10.68	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13		
6		3'-0"	5'-0"			1	15.80	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13	YES	Egress
7		6'-10"	5'-6"			1	41.25	Logic Windows	uPVC	Fixed	Triple	.56	.13		
8		9'-0 1/2"	5'-6"			1	53.68	Logic Windows	uPVC	Fixed	Triple	.56	.13		
9		6'-6"	5'-6"			1	37.62	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13	YES	
0		9'-0"	3'-2"			1	30.24	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13		
1		3'-3"	3'-0"			1	15.82	Logic Windows	uPVC	Fixed	Triple	.56	.13		
2		3'-3"	3'-0"			1	15.82	Logic Windows	uPVC	Fixed	Triple	.56	.13		
3		2'-4"	1'-8"			1	4.33	Logic Windows	uPVC	Tilt-Turn	Triple	.56	.13	YES	
4		4'-0"	2'-0"			1	8.68	Logic Windows	uPVC	Awning	Triple	.56	.13		
5		4'-0"	2'-0"			1	8.68	Logic Windows	uPVC	Fixed	Triple	.56	.13		
6		4'-0"	2'-0"			1	8.68	Logic Windows	uPVC	Fixed	Triple	.56	.13		
7		4'-0"	2'-0"			1	8.68	Logic Windows	uPVC	Awning	Triple	.56	.13		
8		4'-0"	2'-0"			1	8.68	Logic Windows	uPVC	Awning	Triple	.56	.13		
9		4'-4"	4'-11"			1	21.90	Logic Windows	uPVC	Fixed	Triple	.56	.13		
0		6'-1 1/4"	4'-2"			1	26.04	Logic Windows	uPVC	Fixed	Triple	.56	.13		
1		8'-4 1/4"	5'-7"			1	47.48	Logic Windows	uPVC	Fixed	Triple	.56	.13		
						21	406.78 sq ft								

Window Schedule

DOOI	R SCHEDULE										
ID	Double Door	Width	Height	Thickness	Quantity	Manufacturer	Туре	Finish	Glazing	Fire Rating	Notes
01		4'-0"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
02		3'-6"	6'-8"	0'-1 1/4"	1		Solid Core Pocket	Flush Panel			
03		2'-0"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
04		3'-0"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
05		4'-0"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
06		2'-9"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
07		2'-6"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
08		2'-4"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
09		2'-0"	3'-0"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
10		2'-6"	6'-8"	0'-1 1/4"	1		Solid Core Swing	Flush Panel			
11		2'-6"	6'-8"	0'-1 1/4"	1		Solid Core Pocket	Flush Panel			
12		3'-6"	6'-8"	0'-1 1/4"	1		Solid Core Pocket	Flush Panel			
E01		3'-0"	7'-0"	0'-1 1/4"	1		Exterior Swing		Full Lite - Tempered		
E02		3'-0"	7'-0"	0'-1 1/4"	1		Exterior Swing		Full Lite - Tempered		
E03		3'-0"	7'-0"	0'-1 1/4"	1		Exterior Swing		Full Lite - Tempered		
E04		5'-0"	6'-8"	0'-1 1/4"	1						
E05		5'-0"	6'-8"	0'-1 1/4"	1						
					17						

2 Door Schedule



PROJECT:

Stenzel-Walsh New House

PEAKS ISLAND PORTLAND, MAINE 04108

STRUCTURAL:

Casco Bay Engineering
424 Fore Street
Portland, ME 04102
p: 207 842-2888



FOR CONSTRUCTION
PROJECT NO: STZ
DATE: 6/27/16
DRAWN BY: SDF
PHASE: CONSTRUCTION
DOCUMENTS

