LOW ROOF ASSEMBLY (OVER PORCH):
- STANDING SEAM METAL ROOFING (WITH MANUFACTURER RECOMMENDED UNDERLAYMENT / WEATHER RESISTIVE BARRIER AND ICE AND WATER SHIELD)
- ROOF SHEATHING
- 2 x 8 RAFTERS AT 24" OC
- 2 x 6 CEILING JOISTS AT 16" OC W/ BLOCKING AS REQ'D
- 1x FURRING STRAPS
- WOOD BOARD SOFFIT

PORCH FLOOR ASSEMBLY:
- WOOD DECKING
- PT 2 x 8 JOISTS AT 16" OC

CUSTOM GUARDRAIL W/ WOOD LATTICE INFILL

1 BUILDING SECTION (LOOKING WEST)
SCALE: 1/2" = 1'-0"

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 09/18/17

Project:
Peaks Island Cottage
Portland, Maine

Notes:

Architect:
Whitten Architects
37 Silver Street
Portland, Maine 04101
Phone: (207) 774-0111
www.whittenarchitects.com

Landscape Architect:
Soren DeNiord Design Studio
43 Wellwood Road
Portland, Maine 04103
Phone: (207) 400-2450

Civil Engineer:
Walsh Engineering Assoc, Inc.
One Karen Drive, Suite 2A
Westbrook, Maine 04092
Phone: (207) 553-9898

Structural Engineer:
Albert Putnam Associates
183 Park Row
Brunswick, Maine 04011
Phone: (207) 729-6230

General Contractor:
Bunton Construction
87 Middle Road
Cumberland Center,
Maine 04021
Phone: (207) 829-6438

Drawing:

BUILDING SECTION

Date:
June 15, 2017

Issue:

PERMIT SET

A-305

COPYRIGHT - 2017 WHITTEN ARCHITECTS