1 EAST ELEVATION
SCALE: 1/4" = 1' - 0"

2 WEST ELEVATION
SCALE: 1/4" = 1' - 0"

EXTERIOR WINDOW & DOOR SCHEDULE

	SYM.	MANUF.	TYPE	UNIT #	R.O. WIDTH	R.O. HT (SEE NOTE 16)	MATERIAL	INTERIOR FINISH	SCREEN	REMARKS
WINDOWS	A	MARVIN	AWNING	CUAWN4028	3'-5"	2'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	B	MARVIN	(2) AWNING	SEE REMARKS	6'-9 3/8"	4'-11 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT: (2) CUAWN4060 WITH 3/8" MULLION. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	C	MARVIN	DIRECT GLAZE	CRECT41[64.75]	3'-5"	5'-5"	ALUMINUM CLAD WOOD	WHITE OAK	--	--
	D	MARVIN	AWNING	CUAWN4056	3'-5"	4'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	E	MARVIN	DIRECT GLAZE	CRECT6372	5'-4"	5'-11 5/8"	ALUMINUM CLAD WOOD	WHITE OAK	--	--
	F	VELUX	FIXED CURB MOUNTED	#CM3434	3'-1 1/2"	3'-1 1/2"	ALUMINUM CLAD WOOD	PAINTED	--	FIXED CURB MOUNTED SKYLIGHT - CUTSOM FLASH TO ROOF WITH FLASHING TO MATCH ROOF COLOR
	G	MARVIN	(2) CASEMENT	SEE REMARKS	6'-9 3/8"	4'-11 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT: (2) CUCA4060 WITH 3/8" MULLION. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	H	MARVIN	DIRECT GLAZE	CRECT5484	4'-7"	6'-10 7/8"	ALUMINUM CLAD WOOD	WHITE OAK	--	--
	I	MARVIN	AWNING	CUAWN3640	3'-1"	3'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	J	MARVIN	(2) AWNING	SEE REMARKS	6'-9 3/8"	4'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT; (2) CUAWN4056 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	K	MARVIN	AWNING	CUAWN5456	4'-7"	4'-7 5/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	--
	L	MARVIN	DIRECT GLAZE	CRECT4472	3'-9"	5'-11 5/8"	ALUMINUM CLAD WOOD	WHITE OAK	--	--
	M	MARVIN	(2) AWNING	SEE REMARKS	7'-5 3/8"	5'-11 5/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	MULLED UNIT; (2) CUAWN4472 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	N	MARVIN	(2) AWNING (2) DIRECT GLAZE	SEE REMARKS	7'-5 3/8"	8'-3 1/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	MULLED UNIT; (2) CUAWN4472; (2) CRECT4428 WITH 3/8"MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION.
	O	MARVIN	(4) DIRECT GLAZE	SEE REMARKS	7'-5 3/8"	8'-3 3/8"	ALUMINUM CLAD WOOD	WHITE OAK	--	MULLED UNIT; (2) CRECT4472; (2) CRECT4428 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION.
	P	MARVIN	AWNING	CUAWN4444	3'-9"	3'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	Q	MARVIN	(2) DIRECT GLAZE	SEE REMARKS	5'-4"	8'-3 1/8"	ALUMINUM CLAD WOOD	WHITE OAK	--	MULLED UNIT; (1) CRECT6372; (1) CRECT6328 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	R	MARVIN	AWNING	CUAWN4472	3'-9"	5'-11 3/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	--
	S	MARVIN	AWNING	CUAWN2828	2'-5"	2'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	T	MARVIN	(1) AWNING (1) DIRECT GLAZE	SEE REMARKS	4'-7"	6'-10 7/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	MULLED UNIT; (1) CUAWN5428; (1) CRECT5456 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	U	MARVIN	AWNING	CUAWN2828	2'-5"	2'-3 5/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	--
	V	MARVIN	(1) AWNING (1) DIRECT GLAZE	SEE REMARKS	6'-5 3/8"	5'-5"	ALUMINUM CLAD WOOD	WHITE OAK	YES	MULLED UNIT: (1) CUAWN38[64.75]; (1) CRECT38[64.75] WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION.
	W	MARVIN	(1) AWNING (1) DIRECT GLAZE	SEE REMARKS	4'-7"	6'-10 7/8"	ALUMINUM CLAD WOOD	WHITE OAK	YES	MULLED UNIT; (1) CRECT5456; (1) CUAWN5428 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	X	MARVIN	(2) AWNING	SEE REMARKS	7'-5 3/8"	3'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT: (2) CUAWN4444 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	Y	MARVIN	(2) CASEMENT	SEE REMARKS	5'-9 3/8"	3'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT: (1) CUCA2844; (1) CUCA4044 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION
	Z	MARVIN	AWNING	CUAWN4428	3'-9"	2'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	AA	MARVIN	(2) AWNING	SEE REMARKS	6'-9 3/8"	2'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT; (2) CUAWN4028 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION.
	BB	MARVIN	AWNING	CUAWN2828	2'-5"	2'-3 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	--
	CC	MARVIN	(2) AWNING	SEE REMARKS	6'-9 3/8"	4'-7 5/8"	ALUMINUM CLAD WOOD	PAINTED	YES	MULLED UNIT; (2) CUAWN4056 WITH 3/8" MULL. REFER TO EXTERIOR ELEVATIONS FOR WINDOW / MULL CONFIGURATION

	SYM.	MANUF.	TYPE	UNIT #	R.O. WIDTH	R.O. HT (SEE NOTE 13)	MATERIAL	INTERIOR FINISH	SCREEN	REMARKS
DOORS	X01	MARVIN	MULTI-SLIDE	XXXP 14070	19'-1 9/16"	7'-15/16"	ALUMINUM CLAD WOOD	PAINTED	--	CONTEMPORARY HANDLE" - FINISH TBD
	X02	MARVIN	MULTI-SLIDE	XXXP 14086	19'-1 9/16"	8'-6 3/4"	ALUMINUM CLAD WOOD	WHITE OAK	--	CONTEMPORARY HANDLE" - FINISH TBD
	X03	MARVIN	INSWING FRENCH	CMIFD3080 (CONTEMPORARY)	3'-2 7/16"	8'-0"	ALUMINUM CLAD WOOD	WHITE OAK	--	DOOR TO HAVE FACTORY APPLIED 6-9/16" EXTERIOR EXTENSION JAMB; INCLUDE WITH "STANDARD HARDWARE - CONTEMPORARY HANDLE" - FINISH TBD
	X04	MARVIN	INSWING FRENCH	CUIFD3070 (CONTEMPORARY)	3'-2 7/16"	7'-2 1/2"	ALUMINUM CLAD WOOD	PAINTED	--	CONTEMPORARY HANDLE" - FINISH TBD
	X 05	MARVIN	ULTIMATE SLIDING FRENCH	CUSFD 0X0 120R66R	12'-1 1/4"	6'-8"	ALUMINUM CLAD WOOD	PAINTED	--	CONTEMPORARY HANDLE" - FINISH TBD
	X06	MARVIN	ULTIMATE SLIDING FRENCH	CUSFD X0 80R68	8'-0"	6'-10 1/2"	ALUMINUM CLAD WOOD	PAINTED	--	CONTEMPORARY HANDLE" - FINISH TBD

NOTES: (PLEASE READ)

01. WINDOW AND DOOR MANUFACTURER TO BE "MARVIN" (OAE)
02. VERIFY ALL ROUGH OPENING REQUIREMENTS PRIOR TO ROUGH CARPENTRY AND WINDOW ORDER.
03. PROVIDE SHOP DRAWINGS FOR ARCHITECT'S REVIEW PRIOR TO WINDOW AND DOOR ORDER, SHOP DRAWINGS SHOULD INCLUDE ALL INFORMATION PERTINENT TO EACH UNIT. INCLUDE DRAWN ELEVATIONS OF EACH WINDOW / DOOR TYPE, INCLUDING MULL PATTERNS AND SWING DIRECTIONS.
04. WINDOW MANUFACTURER TO DESIGNATE REINFORCED MULLS WHERE REQ'D TO MAINTAIN DESIGN PRESSURE RATINGS - NOTE: UNITS ARE GENERALLY SPACED TO ALIGN FOR A 3/8" MULL. (ALERT ARCHITECT OF ANY POTENTIAL REQ'D SIZING ADJUSTMENTS)
05. WINDOW UNITS TO UTILIZE CLEAR LOW-E 272 GLAZING AND BE TEMPERED WHERE REQ'D BY CODE (NOTE TEMPERED UNITS ON SHOP DRAWINGS FOR ARCHITECTS REVIEW).
06. UNITS SPECIFIED AS EMERGENCY EGRESS UNITS TO TO MEET ALL APPLICABLE EGRESS REQUIREMENTS FOR OPENABLE AREA, ELEVATION FROM FLOOR, AND HARDWARE (SEE EXTERIOR ELEVATIONS).
07. CASEMENT AND AWNING OPERATOR TO BE MANUFACTURER'S "FOLDING HANDLE". HARDWARE FINISH (TBD) - COORDINATE FINAL SELECTION WITH ARCHITECT PRIOR TO ORDERING.
08. SWINGING DOOR HANDLE TO BE MANUFACTURER'S STANDARD "CONTEMPORARY HANDLE" IN TBD HARDWARE FINISH. (PLEASE PRICE AS OIL RUBBED BRONZE PVD)
09. SLIDING DOOR HANDLES TO BE MANUFACTURER'S "CONTEMPORARY SLIDING DOOR HANDLE" IN TBD HARDWARE FINISH. (PLEASE PRICE AS OIL RUBBED BRONZE PVD)
10. MANUFACTURER'S EXTERIOR CLAD COLOR (TBD) - NOTE: PRICE ALL "MARVIN" DOORS AS MANUFACTURER'S "CADET GRAY" FINISH - COORDINATE FINAL COLOR SELECTION WITH ARCHITECT PRIOR TO ORDERING.
11. PAINTING SUBCONTRACTOR TO ADD AN ADDITIONAL PAINT FINISH TO WINDOW FRAMES & SASHES DESIGNATED AS PAINTED.
12. WINDOWS WITH INTERIOR SCREENS TO INCLUDE WOOD VENEERED INSECT SCREEN FRAME WITH FINISH TO MATCH WINDOW FRAMES AND SASHES.
13. INSWING FRENCH DOOR TO HAVE A 4-3/4" BOTTOM RAIL (CONTEMPORARY).
14. MULTI-SLIDE DOORS TO HAVE MANUFACTURER'S "HIGH PERFORMANCE SILL".
15. STICKING: STICKING TO BE MANUFACTURER'S SQUARE STICKING.
16. ADD TO R.O. HEIGHT WHERE REQ'D TO ACCOMMODATE "SILL PAN" INSTALLATION AS RECOMMENDED BY WINDOW / DOOR MANUFACTURER.
17. FOLLOW ALL MANUFACTURER GUIDELINES FOR INSTALLATION. AFTER INSTALLATION, PROVIDE SIGNED LETTER TO OWNER & ARCHITECT FROM MANUFACTURER CONFIRMING THAT INSTALLATION MEETS ALL WARRANTY REQUIREMENTS.

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 09/18/17

Project:

Peaks Island Cottage

Portland, Maine

Notes:

Architect:

Whitten Architects
37 Silver Street
Portland, Maine 04101
Phone: (207) 774-0111
www.whittenarchitects.com

Landscape Architect:

Soren DeNiord Design Studio
43 Wellwood Road
Portland, Maine 04103
Phone: (207) 400-2450

Civil Engineer:

Walsh Engineering Assoc, Inc.
One Karen Drive, Suite 2A
Westbrook, Maine 04092
Phone: (207) 553-9898

Structural Engineer:

Albert Putnam Associates
183 Park Row
Brunswick, Maine 04011
Phone: (207) 729-6230

General Contractor:

Bunton Construction
87 Middle Road
Cumberland Center,
Maine 04021
Phone: (207) 829-6438

Drawing:

EXTERIOR ELEVATIONS & WINDOW SCHEDULE

Date:

June 15, 2017
September 5, 2017 REV-1

Issue:

PERMIT SET

A-201

COPYRIGHT - 2017 WHITTEN ARCHITECTS