



BOX B
 GAF TIMBERLINE HD SHINGLES FASTENED
 W/ 6 NAILS PER SHINGLE
 5/8" OSB
 9/12 COMPONENT ROOF
 2X10 SPF#2 @ 24" @ O.C.
 C/W ICE/SNOW BARRIER AT EAVES
 8" WHITE DRIP EDGE AT RAKES AND AT EAVES
 AIR VENT RIDGE II W/ SHINGLES



BOX A
 GAF TIMBERLINE HD SHINGLES FASTENED
 W/ 6 NAILS PER SHINGLE
 5/8" OSB
 9/12 COMPONENT ROOF
 2X10 SPF#2 @ 24" @ O.C.
 C/W ICE/SNOW BARRIER AT EAVES
 8" WHITE DRIP EDGE AT RAKES AND AT EAVES
 AIR VENT RIDGE II W/ SHINGLES



NOTE ANY & ALL Material shipped loose for the site completion of the manufactured product is ULTIMATELY the SOLE RESPONSIBILITY OF THE BUILDER LISTED BELOW to install and finish.

Builder to check appropriate box, sign, date, and return to N.E.H. Plans not checked, signed, and dated will be returned to Builder and subject to removal from Production Scheduling.

11256	Drawn: 3/10/17 JMS	<p>New England Homes 277 Locust Street, Suite B Dover, NH 03820 www.newenglandhomes.net (telephone):800.800.8831 (fax):603.431.8540</p>
	Revisions	
	3/24/17 RTA	
	4/3/17 RTA	
	4/4/17 RTA	
Sheet: S-106	5/8/17 RTA	Builder: CMH, INC
	6/3/17 RTA	Scale: 1/4"=1'-0"
	7/25/17 RTA	Structure Desc: COLONIAL
LOWER ROOF FRAMING		

PERMIT PLANS

I HAVE REVIEWED THESE PLANS FOR ACCURACY AND HEREBY AUTHORIZE N.E.H. TO DO THE FOLLOWING;

THERE ARE NO CHANGES TO THIS PLAN, RELEASE THE JOB FOR PRODUCTION.

REVISE THE PLANS AS NOTED AND RELEASE THESE PLANS FOR PRODUCTION.

REVISE THESE PLANS AS NOTED AND SEND ME ANOTHER SET OF PERMIT PLANS TO REVIEW.

Signature _____ Date _____
 NEW ENGLAND HOMES INDEPENDENT BUILDERS DULY AUTHORIZED AGENT PER CONTRACT AGREEMENT