



SIDING (BY BUILDER)  
 7/8" ZIP SYSTEM SHEATHING W/  
 SEAMS COVERED  
 W/ ZIP SYSTEM TAPE  
 1/2" x 3/4" CDX PLYWOOD  
 SHEATHING TOP AND BOTTOM  
 PLATE  
 DOUBLE 2x4 SPF STUDS @ 16" O.C.  
 R-30 BLOWN-IN INSULATION W/  
 VAPOR BARRIER PAINT AND  
 INSULHEB  
 7/8" OSB  
 1/2" DRYWALL

DECK TO BE ATTACHED TO HOUSE AS PER 2009  
 IRC, SECTION R502.2.2 DECKS (R502.2.2 THRU  
 R502.2.4)

INSTALL 2-2x2 SPF  
 PERIMETER ON LEFT SIDE FOR  
 BOLTING OF DECK TO  
 PERIMETERS, BY BUILDER

1. ALL MATERIALS BELOW THIS LINE ARE THE  
 RESPONSIBILITY OF THE BUILDER, AND SHALL BE USED IN  
 ACCORDANCE WITH THE MATERIAL MANUFACTURER'S  
 INSTALLATION INSTRUCTIONS, IN CONFORMANCE WITH ALL  
 APPLICABLE BUILDING CODES. ANY DETAILS/DRAWINGS  
 REFERENCING MATERIAL NOT SUPPLIED BY M.E.H. ARE  
 FOR REFERENCE ONLY, AND SHOULD BE APPROVED BY  
 THE LOCAL BUILDING INSPECTOR PRIOR TO USE. ALL  
 SUCH MATERIAL/CONSTRUCTION MUST BE SITE INSPECTED.

T.R. ARNOLD & ASSOCIATES, INC. 4781 Chase Dr. Biddeford, ME 04011  
 (State) **MAINE**  
 Accredited Evaluation and Inspection Agency  
 This document is certified as being in conformance with  
 LISTED CODES.  
 Approved by *[Signature]*  
 Aug 8, 2017  
 Approval of this document does not authorize or approve  
 any contractor or do not constitute a representation of  
 applicable State Laws.  
 THIS APPROVAL IS LIMITED TO  
 FACTORY-BUILT MODULES ONLY.

NOTE: MFR & ALL materials shipped hereon for the sole completion of the manufactured product is ULTIMATELY the SOLE  
 RESPONSIBILITY OF THE MODULE LISTED BUILDER to install and finish.

Permit to check appropriate fire, safety, etc., and submit to MHA. Plans and elevations, signed, sealed and dated will be returned  
 to builder and subject to review from Production Monitoring.

**PERMIT PLANS**

I HAVE REVIEWED THESE PLANS FOR ACCURACY AND HEREBY AUTHORIZE M.E.H. TO DO THE FOLLOWING:

THERE ARE NO CHANGES TO THIS PLAN, RELEASE THE JOB FOR PRODUCTION.

REVISE THE PLANS AS NOTED AND RELEASE THESE PLANS FOR PRODUCTION.

REVISE THESE PLANS AS NOTED AND SEND THE ANOTHER SET OF PERMIT PLANS TO REVIEW.

Signature \_\_\_\_\_ Date \_\_\_\_\_  
 NEW ENGLAND HOMES INDEPENDENT BUILDERS DULY AUTHORIZED AGENT PER CONTRACT AGREEMENT

**New England Homes**  
 277 Louisa Street, Suite B  
 Dover, NH 03820  
 www.newenglandhomes.net  
 (telephone) 603.690.8881  
 (fax) 603.691.9840

**CMH, INC**  
 Structural Steel  
 3/16" x 1'-0"

**COLONIAL STAIR SECTION**

Drawn	Job
9/17	Revisions
9/27	ITA
4/17	ITA
4/17	ITA
8/17	ITA
8/17	ITA
7/17	ITA