Inspections Division
Date: 12/29/14

NOTES:
1.)ALL WOOD FRAMING MEMBERS THAT REST ON CONCRETE OR MASONRY EXTERIOR WALLS AND ARE LESS THAN 8" FROM THE EXPOSED GROUND SHALL BE OF A ROT RESISTANT MATERIAL

2.)ALL WOOD JOISTS OR THE BOTTOM OF A WOOD STRUCTURAL FLOOR WHEN CLOSER THAN 18", OR WOOD GIRDERS WHEN CLOSER THAN 12", TO THE EXPOSED GROUND, SHALL BE OF A ROT REISTANT MATERIAL.

3.)NEW WOOD SIDING AND/OR SHEATHING TO BE ABOVE GRADE A MINIMUM OF 6" OR ELSE OF A ROT RESISTANT MATERIAL.

5.) SPECIFICATIONS FOR FOUNDATION WORK:

A) CONTRACTOR TO SURVEY EXISTING POSTS ANDFOOTINGS THAT DO NOT COMPLY WITH ANY OF THE FOLLOWING CRITERIA:
1) POST MIN. SIZE 4X4
2) POST NO MORE THAN 1/4" OUT OF PLUMB
3) POST IS PRESSURE TREATED
4) POST BASE SIMPSON AB-TYPE OR EQUAL INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.
5) TOP OF FOOTING/PIER IS NO MORE THAN 1/2" OUT OF LEVEL

B) NEW/REPLACEMENT POST FOOTINGS SHALL BE MIN 4'-0" DEEP ON SOIL (OR PINNED TO ROCK) WITH 24"Ø X 8" THICK FOOTING. PIERS TO BE MIN. 10Ø ROUND DOWELED TO FOOTING WITH (2) #3 24" LONG W/ 4" HOOK & (3) #3 VERTICAL BARS & #3 HOOPS AT 8" VERTICAL SPACING

5.) SPECIFICATIONS FOR FOUNDATION WORK (CONT'D):

C) TYPICAL NEW EXTERIOR STAIR FOOTINGS SHALL BE MIN 4'-0" DEEP ON SOIL (OR PINNED TO ROCK) WITH 12" X 6" FOOTING (R403.1.1) 8" HOLLOW CMU FROSTWALL (R404.1.1), 2X8 P.T. SOLE PLATE ANCHORED TO FROSTWALL ACCORDING TO R403.1.6 (FULLY GROUT CELLS OF TOP COURSE OF CMU TO HOLD ANCHOR BOLTS) ADJUST LAYOUTS AS NECESSARY TO MAINTAIN MIN RUN OF 10" AND MAXIMUM RISE OF 7 3/4"



A Proposed Cross Section
1/4"=1'-0"

Rachel Conly
Architectural Design

26 Sterling Street
Peaks Island, Maine 04108
207.766.5625

Proposed
Cross Section

PROJECT

Arnold Residence
398 Island Ave.
Peaks Island, ME

DATE	REVISED
06.02.14	12.01.14
SCALE 1/4"=1'-0"	DRAWN BY Rachel & Harvey

NOTES

A13