

SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Dept. Health & Human Services
Div of Environmental Health, 11 SHS
(207) 287-5672 FAX (207) 287-3165

PROPERTY LOCATION		>>CAUTION: LPI APPROVAL REQUIRED<<	
City, Town, or Plantation	PORTLAND (PEAKS ISLAND)		
Street or Road	53 ISLAND AVENUE		
Subdivision, Lot #			
OWNER/APPLICANT INFORMATION		Town/City _____ Permit # _____	
Name (last, first, MI)	N/F MACLEOD KRISTEN		Date Permit Issued ___/___/___ Fee \$ _____ Double Fee Charged []
	<input checked="" type="checkbox"/> Owner <input type="checkbox"/> Applicant		LPI # _____
Mailing Address of Applicant	MONICA STEVENSON 548 ISLAND AVENUE PEAKS ISLAND, MAINE 04108		
Daytime Tel. #	Municipal Tax Map # 90 Lot # R12		
OWNER OR APPLICANT STATEMENT		CAUTION: INSPECTION REQUIRED	
I state and acknowledge that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Department and/or Local Plumbing Inspector to deny a permit.		I have inspected the installation authorized above and found it to be in compliance with the Subsurface Wastewater Disposal Rules Application.	
Signature of Owner/Applicant: <u>Monica Stevenson</u> Date: <u>9/16/12</u>		(1st) Date Approved _____ Local Plumbing Inspector Signature _____ (2nd) Date Approved _____	

PERMIT INFORMATION	
TYPE OF APPLICATION <input type="checkbox"/> 1. First Time System <input checked="" type="checkbox"/> 2. Replacement System Type Replaced: <u>CESSPOOL</u> Year Installed: <u>PRE-1974</u> <input type="checkbox"/> 3. Expanded System <input type="checkbox"/> a. <25% Expansion <input type="checkbox"/> b. >25% Expansion <input type="checkbox"/> 4. Experimental System <input type="checkbox"/> 5. Seasonal Conversion	THIS APPLICATION REQUIRES <input checked="" type="checkbox"/> 1. No Rule Variance <input type="checkbox"/> 2. First Time System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 3. Replacement System Variance <input type="checkbox"/> a. Local Plumbing Inspector Approval <input type="checkbox"/> b. State & Local Plumbing Inspector Approval <input type="checkbox"/> 4. Minimum Lot Size Variance <input type="checkbox"/> 5. Seasonal Conversion Permit
SIZE OF PROPERTY +/- <u>10,000</u> <input checked="" type="checkbox"/> SQ. FT. <input type="checkbox"/> ACRES	DISPOSAL SYSTEM TO SERVE <input checked="" type="checkbox"/> 1. Single Family Dwelling Unit, No. of Bedrooms: <u>4</u> <input type="checkbox"/> 2. Multiple Family Dwelling, No of Units: _____ <input type="checkbox"/> 3. Other: _____ (specify) Current Use <input checked="" type="checkbox"/> Seasonal <input type="checkbox"/> Year Round <input type="checkbox"/> Undeveloped
SHORELAND ZONING <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	DISPOSAL SYSTEM COMPONENTS <input checked="" type="checkbox"/> 1. Complete Non-Engineered System <input type="checkbox"/> 2. Primitive System (graywater & alt toilet) <input type="checkbox"/> 3. Alternative Toilet, specify: _____ <input type="checkbox"/> 4. Non-Engineered Treatment Tank (only) <input type="checkbox"/> 5. Holding Tank, _____ gallons <input type="checkbox"/> 6. Non-Engineered Disposal Field (only) <input type="checkbox"/> 7. Separated Laundry System <input type="checkbox"/> 8. Complete Engineered System (2000gpd+) <input type="checkbox"/> 9. Engineered Treatment Tank (only) <input type="checkbox"/> 10. Engineered Disposal Field (only) <input type="checkbox"/> 11. Pre-treatment, specify: _____ <input type="checkbox"/> 12. Miscellaneous components
TYPE OF WATER SUPPLY <input type="checkbox"/> 1. Drilled Well <input type="checkbox"/> 2. Dug Well <input type="checkbox"/> 3. Private <input checked="" type="checkbox"/> 4. Public <input type="checkbox"/> 5. Other: _____	

DESIGN DETAILS (SYSTEM LAYOUT SHOWN ON PAGE 3)			
TREATMENT TANK <input checked="" type="checkbox"/> 1. Concrete <input checked="" type="checkbox"/> a. Regular <input type="checkbox"/> b. Low Profile <input type="checkbox"/> 2. Plastic <input type="checkbox"/> 3. Other: _____ CAPACITY: <u>1000</u> GAL.	DISPOSAL FIELD TYPE & SIZE <input type="checkbox"/> 1. Stone Bed <input type="checkbox"/> 2. Stone Trench <input checked="" type="checkbox"/> 3. Proprietary Device <input type="checkbox"/> a. Cluster array <input checked="" type="checkbox"/> c. Linear <input checked="" type="checkbox"/> b. Regular <input type="checkbox"/> d. H-20 loaded <input type="checkbox"/> 4. Other: _____ SIZE: <u>1200</u> <input checked="" type="checkbox"/> sq. ft. <input type="checkbox"/> lin. ft. <u>25</u> ELJEN IN-DRAIN UNITS	GARBAGE DISPOSAL UNIT <input checked="" type="checkbox"/> 1. No <input type="checkbox"/> 2. Yes <input type="checkbox"/> 3. Maybe If Yes or Maybe, specify one below: <input type="checkbox"/> a. Multi-compartment tank <input type="checkbox"/> b. _____ tanks in series <input type="checkbox"/> c. Increase in tank capacity <input type="checkbox"/> d. Filter on tank outlet	DESIGN FLOW <u>360</u> gallons per day BASED ON: <input checked="" type="checkbox"/> 1. Table 4A (dwelling unit(s)) <input type="checkbox"/> 2. Table 4C (other facilities) SHOW CALCULATIONS for other facilities 4 BEDROOMS AT 90 GALLONS PER DAY EACH <input type="checkbox"/> 3. Section 4G (meter readings) ATTACH WATER-METER DATA
SOIL DATA & DESIGN CLASS PROFILE <u>3</u> / <u>C</u> at Observation Hole # <u>TP 1</u> Depth <u>34</u> " of Most Limiting Soil Factor	DISPOSAL FIELD SIZING <input type="checkbox"/> 1. Medium - 2.6 sq.ft./gpd <input checked="" type="checkbox"/> 2. Medium-Large - 3.3 sq.ft./gpd <input type="checkbox"/> 3. Large - 4.1 sq.ft./gpd <input type="checkbox"/> 4. Extra-Large - 5.0 sq.ft./gpd	EFFLUENT/EJECTOR PUMP <input checked="" type="checkbox"/> 1. Not required <input type="checkbox"/> 2. May be required <input type="checkbox"/> 3. Required Specify only for engineered systems: DOSE: _____ gallons	LATITUDE AND LONGITUDE at center of disposal area Lat. <u>N 43</u> d <u>40</u> m <u>8</u> s Lon. <u>W 70</u> d <u>11</u> m <u>69</u> s if g.p.s., state margin of error

SITE EVALUATOR STATEMENT	
I Certify that on <u>9/7/12</u> (date) I completed a site evaluation on this property and state that the data reported is accurate and that the proposed system is in compliance with the Subsurface Wastewater Disposal Rules (10-144A CMR 241).	
Site Evaluator Signature: <u>Albert Frick</u>	SE #: <u>163</u> Date: <u>9/10/2012</u>
ALBERT FRICK Site Evaluator Name Printed	(207) 839-5563 Telephone Number
ALBERT@ALBERTFRICK.COM E-mail Address	



SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Department of Human Services
 Division of Health Engineering, Station 10 SHS
 (207) 287-5672 FAX (207) 287-4172

Town, City, Plantation: **PORTLAND (PEAKS ISLAND)** Street, Road Subdivision: **531 ISLAND AVENUE** Owner's Name: **N/F MACLEOD (FOR MONICA STEVENSON)**

SITE PLAN Scale 1" = **40** Ft. or as shown

SITE LOCATION PLAN (Attach Map from Maine Atlas for New System Variance)



NOTE : PROPERTY INFORMATION APPROXIMATED PER TOWN TAX MAP AND AERIAL PHOTOGRAPH VERIFY LOT LINES TO ASSURE PROPER SETBACKS VERIFY WATER LINE LOCATION TO ASSURE PROPER SETBACKS. RELOCATE IF NECESSARY

SOIL DESCRIPTION AND CLASSIFICATION (Location of Observation Holes Shown Above)

Observation Hole TP 1 Test Pit Boring
 _____ " Depth of Organic Horizon Above Mineral Soil

DEPTH BELOW MINERAL SOIL SURFACE (inches)	Texture	Consistency	Color	Mottling
0	SANDY		DARK	
	LOAM		BROWN	
10	LOAMY		DARK YEL.	
	SAND		BROWN	
		FRIABLE		
20	MEDIUM		YELLOWISH	
	SAND		BROWN	
30				
40	LOAMY			COMMON,
	FINE	FIRM	OLIVE	DISTINCT
	SAND		BROWN	
50	LIMIT OF EXCAVATION			

Soil Classification	Slope	Limiting Factor	<input type="checkbox"/> Ground Water
<u>3</u> Profile	<u>C</u> Condition	<u>34</u> %	<input type="checkbox"/> Restrictive Layer
			<input type="checkbox"/> Bedrock
			<input type="checkbox"/> Pit Depth

Observation Hole _____ Test Pit Boring
 _____ " Depth of Organic Horizon Above Mineral Soil

DEPTH BELOW MINERAL SOIL SURFACE (inches)	Texture	Consistency	Color	Mottling
0				
10				
20				
30				
40				
50				

Soil Classification	Slope	Limiting Factor	<input type="checkbox"/> Ground Water
Profile	Condition	%	<input type="checkbox"/> Restrictive Layer
			<input type="checkbox"/> Bedrock
			<input type="checkbox"/> Pit Depth

Albert Frick
 Site Evaluator Signature

163
 SE *

9/10/2012
 Date

SUBSURFACE WASTEWATER DISPOSAL SYSTEM APPLICATION

Maine Department of Human Services
 Division of Health Engineering, Station 10 SHS
 (207) 287-5672 FAX (207) 287-4172


Town, City, Plantation
PORTLAND (PEAKS ISLAND)

Street, Road, Subdivision
531 ISLAND AVENUE

Owner's Name
N/F MACLEOD (FOR MONICA STEVENSON)

SUBSURFACE WASTEWATER DISPOSAL PLAN

SCALE 1" = 20 FT.



FILL REQUIREMENTS

Depth of Fill (Upslope) : 1"-8"
 Depth of Fill (Downslope) : 4"-9"
 DEPTHS AT CROSS-SECTION (shown below)

CONSTRUCTION ELEVATIONS

Finished Grade Elevation
 Top of Distribution Pipe or Proprietary Device
 Bottom of Disposal Area


SEE
 DETAIL
 BELOW

ELEVATION REFERENCE POINT

Location & Description BOTTOM OF BASEMENT WINDOW SILL, 15" ABOVE GRADE
 Reference Elevation is: 0.0" or -----

SCALE:
 VERTICAL: 1" = 5'
 HORIZONTAL: 1" = 10'

DISPOSAL AREA CROSS SECTION



SEE ELJEN IN-DRAIN MANUAL ON SERIAL DISTRIBUTION ON SLOPES FOR PROPER PIPING

DEPTH BELOW ERP:	ROW 1	2	3	4	5
FINISHED GRADE	-26"	-30"	-34"	-38"	-42"
CLEAN FILL	-38"	-42"	-46"	-50"	-54"
GEOTEXTILE FABRIC OVER 4" DIA. PERF. PIPE	-42"	-46"	-50"	-54"	-58"
ELJEN IN-DRAIN UNIT	-49"	-53"	-57"	-61"	-65"
GRVELLY COARSE SAND	-55"	-59"	-63"	-67"	-71"

Albert Frick
 Site Evaluator Signature

163
 SE *

9/10/2012
 Date

Page 3 of 3
 HHE-200 Rev. 10/02



Albert Frick Associates, Inc.

Soil Scientists & Site Evaluators

95A County Road Gorham, Maine 04038
(207) 839-5563

PORTLAND (PEAKS ISLAND) 531 ISLAND AVENUE N/F MACLEOD (FOR MONICA STEVENSON)

TOWN LOCATION APPLICANT'S NAME

- 1) The Plumbing and Subsurface Wastewater Disposal Rules adopted by the State of Maine, Division of Health and Human Services pursuant to 22 M.R.S.A. § 42 (the "Rules") are incorporated herein by reference and made a part of this application and shall be consulted by the owner/applicant, the system installer and/or building contractor for further construction details and material specifications. The system Installer should contact Albert Frick Associates, Inc. 839-5563, if there are any questions concerning materials, procedures or designs. The system installer and/or building contractor installing the system shall be solely responsible for compliance with the Rules and with all state and municipal laws and ordinances pertaining to the permitting, inspection and construction of subsurface wastewater disposal systems.
- 2) This application is intended to represent facts pertinent to the Rules only. It shall be the responsibility of the owner/applicant, system Installer and/or building contractor to determine compliance with and to obtain permits under all applicable local, state and/or federal laws and regulations (including, without limitation, Natural Resources Protection Act, wetland regulations, zoning ordinances, subdivision regulations, Site Location of Development Act and Minimum Lot Size law) before installing this system or considering the property on which the system is to be installed a "buildable" lot. It is recommended that a wetland scientist be consulted regarding wetland regulations. Prior to the commencement of construction/installation, the local plumbing inspector or Code Enforcement Officer shall inform the owner/applicant and Albert Frick Associates, Inc of any local ordinances which are more restrictive than the Rules in order that the design may be amended. All designs are subject to review by local, state and/or federal authorities. Albert Frick Associates, Inc.'s liability shall be limited to revisions required by regulatory agencies pursuant to laws or regulations in effect at the time of preparation of this application.
- 3) All information shown on this application relating to property lines, well locations, subsurface structures and underground facilities (such as utility lines, drains, septic systems, water lines, etc.) are based upon information provided by the owner/applicant and has been relied upon by Albert Frick Associates, Inc. in preparing this application. The owner/applicant shall review this application prior to the start of construction and confirm this information. Well locations on abutting properties but not readily visible above grade should be confirmed by the owner/applicant prior to system installation to assure minimum setbacks.
- 4) Installation of a garbage (grinder) disposal is not recommended. If one is installed, an additional 1000 gallon septic tank or a septic tank filter shall be connected in series to the proposed septic tank. Risers and covers should be installed over the septic tank outlet per the "Rules" to allow for easy maintenance of filter.
- 5) The septic tank should be pumped within two years of installation and subsequently as recommended by the pump service, but in no event should the septic tank be pumped less often than every three years.
The system user shall avoid introducing kitchen grease or fats into this system. Chemicals such as septic tank cleaners and/or chlorine (such as from water treatment units) and controlled or hazardous substances shall not be disposed of in this system. Additives such as yeast or enzymes are discouraged, since they have not been proven to extend system life.
- 6) All septic tanks, pump stations and additional treatment tanks shall be installed to prevent ground water and surface water infiltration. Risers and covers should be properly installed to provide access while preventing surface water intrusion to within 6" of a finished ground surface.
Vehicular traffic over disposal system is prohibited unless specifically designed with H-20 rated components.

ATTACHMENT TO SUBSURFACE WASTEWATER DISPOSAL APPLICATION

PORTLAND (PEAKS ISLAND)

531 ISLAND AVENUE


N/F MACLEOD (FOR MONICA STEVENSON)

TOWN

LOCATION

APPLICANT'S NAME

- 7) The actual waste water flow or number of bedrooms shall not exceed the design criteria indicated on this application without a re-evaluation of the system as proposed
- 8) The general minimum setbacks between a well (public or private) and septic system serving a single family residence is 100-300 feet, unless the local municipality has a more stringent requirement. A well installed by an abutter within the minimum setback distances prior to the issuance of a permit for the proposed disposal system may void this design.
- 9) When a gravity system is proposed: BEFORE CONSTRUCTION/INSTALLATION BEGINS, the system installer or building contractor shall review the elevations of all points given in this application and the elevation of the existing and/or proposed building drain and septic tank inverts for compatibility to minimum pitch requirements. In gravity systems, the invert of the septic tank(s) outlet(s) should be at least 4 inches above the invert of the distribution box outlet at the disposal area.
- 10) When an effluent pump is required: Pump stations should be sized per manufacturer's specifications to meet lift requirements and friction loss. Provisions shall be made to make certain that surface and ground water does not enter the septic tank or pump station, by sealing/grouting all seams and connections, and by placement of a riser and lid at or above grade. An alarm device warning of a pump failure shall be installed. Also, when pumping is required of a chamber system, install a 'T' connection in the distribution box and place 3 inches of stone or a splash plate in the first chamber. Insulate gravity pipes, pump lines and the distribution box as necessary to prevent freezing.
- 11) On all systems, remove the vegetation, organic duff and old fill material from under the disposal area and any fill extension. Additional fill beyond indicated on plan may be necessary to replace organic matter. On sites where the proposed system is to be installed in natural soil, scarify the bottom and sides of the excavated disposal area with a rake. Do not use wheeled equipment on the scarified soil surface. For systems installed in fill, scarify the native soil by roto-tilling or scarifying with teeth of backhoe to a depth of at least 8 inches over the entire disposal and fill extension area to prevent glazing and to promote fill bonding. Place fill in loose layers no deeper than 8 inches and compact before placing more fill (this ensures that voids and loose pockets are eliminated to minimize the chance of leakage or differential settling). Do not use wheeled equipment on the scarified soil area until after 12 inches of fill is in place. Keep equipment off proprietary devices. Divert the surface water away from the disposal area by ditching or shallow landscape swales.
- 12) Unless noted otherwise, fill shall be gravelly coarse sand, which contains no more than 5% fines (silt and clay). Crushed stone shall be clean and free of any rock dust from the crushing process.
- 13) Do not install systems on loamy, silty, or clayey soils during wet periods since soil smearing/glazing may seal off the soil interface.
- 14) Seed all filled and disturbed surfaces with perennial grass seed, with 4" min. soil or soil amendment mix suitable for growing, then mulch with hay or equivalent material to prevent erosion. Alternatively, bark or permanent landscape mulch may be used to cover system. Woody trees or shrubs are not permitted on the disposal area or fill extensions.
- 15) If an advanced wastewater treatment unit is part of the design, the system shall be operated and maintained per manufacturer's specifications.



Albert Frick Associates, Inc.
Soil Scientists & Site Evaluators

95A County Road Gorham, Maine 04058