

Subsurface Inspection Requirements for 73 Sargent St. Peaks Island

CBL: 090 U017001

City Permit # 2013-01338

State ID# 11971

Septic Field

1. After Site Preparation: Septic field and extension inspection for bottom preparation/scarification to verify removal of vegetation and roughened surface, established transitional horizon and erosion and sedimentation control measures.
2. Prior to covering the system: Inspection of system components including stone, pipes or proprietary devices, tanks, hay, filter fabric, and fill beneath and beside the disposal area before backfill. Also included are curtain drains, diversion ditches, berms or other measures outlined in the design.