


- NOTES:
1. ALL WOOD FRAMING MEMBERS THAT REST ON CONCRETE OR MASONRY EXTERIOR WALLS AND ARE LESS THAN 8' FROM THE EXPOSED GROUND SHALL BE OF A ROT RESISTANT MATERIAL.
 2. ALL WOOD JOISTS OR THE BOTTOM OF A WOOD STRUCTURAL FLOOR WHEN CLOSER THAN 18", OR WOOD GIRDERS WHEN CLOSER THAN 12", TO THE EXPOSED GROUND, SHALL BE OF A ROT RESISTANT MATERIAL.
 3. NEW WOOD SIDING AND/OR SHEATHING TO BE ABOVE GRADE A MINIMUM OF 6" OR ELSE OF A ROT RESISTANT MATERIAL.
 4. ALL DECK/STAIR FRAMING/DECKING TO BE OF ROT RESISTANT WOOD.

- 5.) SPECIFICATIONS FOR FOUNDATION WORK:
- A) CONTRACTOR TO SURVEY EXISTING POSTS AND FOOTINGS THAT DO NOT COMPLY WITH ANY OF THE FOLLOWING CRITERIA:
 - 1) POST MIN. SIZE 4X4
 - 2) POST NO MORE THAN 1/4" OUT OF PLUMB
 - 3) POST IS PRESSURE TREATED
 - 4) POST BASE SIMPSON AB-TYPE OR EQUAL INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.
 - 5) TOP OF FOOTING/PIER IS NO MORE THAN 1/2" OUT OF LEVEL

- 5.) SPECIFICATIONS FOR FOUNDATION WORK (cont'd):
- B) NEW/REPLACEMENT POST FOOTINGS SHALL BE MIN 4'-0" DEEP ON SOIL (OR PINNED TO ROCK) WITH 24"Ø X 8" THICK FOOTING. PIERS TO BE MIN. 10Ø ROUND, DOWELED TO FOOTING WITH (2) #3 24" LONG W/ 4" HOOK & (3) #3 VERTICAL BARS & #3 HOOPS AT 8" VERTICAL SPACING, PROVIDE (1) ANCHOR BOLT ACCORDING TO R403.1.6, CENTERED IN FOOTING, FOR USE WITH APPROPRIATE POST BASE HARDWARE.
 - C) TYPICAL NEW EXTERIOR STAIR FOOTINGS SHALL BE MIN 4'-0" DEEP ON SOIL (OR PINNED TO ROCK) WITH 12" X 6" FOOTING (R403.1.1) 8" HOLLOW CMU FROSTWALL (R404.1.1), 2X8 P.T. SOLE PLATE ANCHORED TO FROSTWALL ACCORDING TO R403.1.6 (FULLY GROUT CELLS OF TOP COURSE OF CMU TO HOLD ANCHOR BOLTS)



(A) Proposed Porch Foundation
1/4" = 1'-0"

(B) Proposed Porch Floor/Stair Framing
1/4" = 1'-0"

(C) Proposed Porch Roof Framing
1/4" = 1'-0"

Rachel Conly
Architectural Design

26 Sterling Street
Peaks Island, Maine 04108
207.766.5625

**Proposed
Foundation,
Porch Floor,
Stair,
and Roof
Framing Plans**

PROJECT

**Braun Hogan
Residence
265 Pleasant Ave.
Peaks Island, ME**

DATE 07.29.14

REVISED

SCALE 1/4" = 1'-0"

DRAWN BY
**Rachel &
Harvey**

NOTES

S1