



- STAIRS:** REBUILD EXISTING STAIR (ROTTING)
FOOTPRINT IS TO BE IDENTICAL TO EXISTING STAIR.
- CODE CONFORMANCE (IRC 2009) IS ACHIEVABLE.
- 2x12 PT. STRINGERS @ 21" OC ±
 - CLOSED SOUND PAINTED RISERS (PINS OF SIM)
 - 1x4 FIR TREES w/ 1" NOSINGS
 - 10" RUN + NOSING, 7 7/16" UNIFORM RISERS (MUST BE LESS THAN 7 7/4")
 - HANDRAIL / GUARDRAIL: 36" HIGH, BOTH SIDES, 1 1/4" SQ. BALUSTERS (MIN 4" CLEAR OR LESS CLEAR SPACING)
 - 4x4 WRC MEMBERS, 2 1/4" x 1 1/2" FAN CAP + SUBRAIL (6" BALU TEST @ SUBRAIL TO RISER/TREAD)

STONE:
EXISTING STONE + CONCRETE STEPS + RETAINING;
MAJON IS TO REPAIR (OR REBUILD AS REQUIRED.)

6 NORTH ELEVATION / SECTION