WINDOW and DOOR Schedule and HEADER SCHEDULE				
Location	Type	opening	quantity	Header Size
1st floor front	Entry door	4'-0" x 6'-8"	1	(3) 2x10
1st floor front (Dining and Lng rooms)	Casement mulledx2 transcom	3'-0" x 4'-8"	4	(3) 2x10
1st floor, left (dining)	double hung	3'-0" x 4'-8"	1	(3) 2x8
1st floor, right (living room)	double hung	3'-0" x4'-8"	2	(3) 2x8
1st floor, left (kitchen and mud room)	double hung	2'-0" x 3'-0"	3	(3) 2x6
1st floor, left (kitchen)	transcom	6'-0"x 1'-0"	1	(3) 2x10
1st floor, left (kitchen and mud room)	entry door (tempered glass)	3'-0" x 6'-8"	2	(3) 2x8
1st floor,back (kitchen)	Casement mulledx3	2'-0" x 3'-0"	3	(3) 2x8
1st floor , back (living room)	slider door (tempered glass)	6'-0"-6'-8"	1	(3) 2x10
2nd floor left(bedroom)	double hung	2'-6" x 3'-0"	2	(3) 2x6
2nd floor right (bathroom and loft)	double hung	2'-6" x3'-0"	2	(3) 2x6
2nd floor back top of stair	double hung mulled x2, semi circle	2'-0" x 4'-0"	1	(3) 2x8
2nd floor back bathroom	double hung	2'-0" x 3'-0"	1	(3) 2x6
2nd floor back bedroom	slider door (tempered glass, Egress)	5'-0" x 6"-6"	1	(3)2x8
total			25	

CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/27/15