FIRST FLOOR FRAMING PLAN

1/4" = 1'-0"

PLAN NOTES:

1. FLOOR JOISTS WITHIN 18" OF FINISHED GRADE SHALL BE PRESSURE TREATED.
2. FLOOR BEAMS AND GIRDERS WITHIN 12" OF FINISHED GRADE SHALL BE PRESSURE TREATED.
3. COORD. T/ FLOOR ELEVATION w/ ARCH.

STATE OF MAINE
MATTHEW J. MILLER
No. 11286
LICENSED
PROFESSIONAL ENGINEER

ISSUED FOR PERMIT APRIL 8, 2015

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/21/15

ATTARDO PONDELIS ARCHITECTURE
81 Bridge Street
Suite 100
Yarmouth, ME 04096
207.846.3043

M2 Structural Engineering
23 Thornbery Way
Windham, ME 04062
(207) 892-0983
info@m2structuralengineering.com

SHAW BOATHOUSE
Little Diamond Island, Maine

First Floor Framing Plan
Scale: As Noted
Drawn by: MJM
Date: 04.08.2015
Revisions:

S1.1