

City of Portland, Maine – Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

Location of Construction: Rockledge Ave L.D.I.		Owner: Plum., L.W & G. Ann		Phone: 766-5098	Permit No: 980778
Owner Address: 1613 Cross Church Rd Asheboro, NC 27203		Lessee/Buyer's Name:		Phone:	BusinessName:
Contractor Name:		Address:		Phone:	
Past Use: 1-fam	Proposed Use:		COST OF WORK: \$ 2,500.00	PERMIT FEE: \$ 35.00	
Proposed Project Description: Screened in porch with storage area			FIRE DEPT. <input type="checkbox"/> Approved <input type="checkbox"/> Denied	INSPECTION: Use Group: 1-2 Type: 59 <i>200215</i>	
			PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)		Signature: <i>H. J. [unclear]</i>
Action: Approved <input type="checkbox"/>			Approved with Conditions: <input type="checkbox"/>		
Denied <input type="checkbox"/>			Signature: _____ Date: _____		
Permit Taken By: NG		Date Applied For: 16 July 1998			

PERMIT ISSUED
Permit Issued:
JUL 20 1998
CITY OF PORTLAND

Zone: **IR-2** CBL: **105-Y-012+1**
Zoning Approval: **OK 7/17/98**
Special Zone or Reviews:
 Shoreland *305-685 [unclear]*
 Wetland *11/1/98*
 Flood Zone *10-14*
 Subdivision *2-10-C*
 Site Plan major minor mm

Zoning Appeal
 Variance
 Miscellaneous
 Conditional Use
 Interpretation
 Approved
 Denied

Historic Preservation
 Not in District or Landmark
 Does Not Require Review
 Requires Review

Action:
 Approved
 Approved with Conditions
 Denied

Date: *[Signature]*

- This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
- Building permits do not include plumbing, septic or electrical work.
- Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

SIGNATURE OF APPLICANT _____ ADDRESS: _____ DATE: **17 July 1998** PHONE: _____

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE _____ PHONE: _____

White-Permit Desk Green-Assessor's Canary-D.P.W. Pink-Public File Ivory Card-Inspector

CEO DISTRICT *[Signature]*

PERMIT ISSUED WITH REQUIREMENTS

BUILDING PERMIT REPORT

DATE: 17 July 98 ADDRESS: Rockledge Ave. L.D.I. (105-4-0124)
 REASON FOR PERMIT: TO CONSTRUCT PORCH / STORAGE AREA + 1st
 BUILDING OWNER: Ann Plum
 CONTRACTOR: owner
 PERMIT APPLICANT: ↑
 USE GROUP A-3 BOCA 1996 CONSTRUCTION TYPE 5B

CONDITION(S) OF APPROVAL

This Permit is being issued with the understanding that the following conditions are met:

Approved with the following conditions: *1 *8 *10 *20, *29 *30

- ~~X~~1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection)
- 2.5. Foundation drain shall be placed around the perimeter of a foundation that consists of gravel or crushed stone containing not more than 10 percent material that passes through a No. 4 sieve. The drain shall extend a minimum of 12 inches beyond the outside edge of the footing. The thickness shall be such that the bottom of the drain is not higher than the bottom of the base under the floor, and that the top of the drain is not less than 6 inches above the top of the footing. The top of the drain shall be covered with an approved filter membrane material. Where a drain tile or perforated pipe is used, the invert of the pipe or tile shall not be higher than the floor elevation. The top of joints or top of perforations shall be protected with an approved filter membrane material. The pipe or tile shall be placed on not less than 2" of gravel or crushed stone, and shall be covered with not less than 6" of the same material.
3. Precaution must be taken to protect concrete from freezing.
4. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
5. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of ½ inch gypsum board or the equivalent applied to the garage means of ½ inch gypsum board or the equivalent applied to the garage side. (Chapter 4 Section 407.0 of the BOCA/1996)
6. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993).
7. Sound transmission control in residential building shall be done in accordance with Chapter 12 section 1214.0 of the city's building code.
- ~~X~~8. **Guardrails & Handrails:** A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", except Use Group R which is 36". In occupancies in Use Group A, B, H-4, I-1, I-2 M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38", Use Group R-3 shall not be less than 30", but not more than 38".) Handrail grip size shall have a circular cross section with an outside diameter of at least 1 1/4" and not greater than 2".
9. Headroom in habitable space is a minimum of 7'6".
- ~~X~~10. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 3/4" maximum rise. ~~All other Use group minimum 11" tread - 7" maximum rise.~~
11. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6' 8")
12. Every sleeping room below the fourth story in buildings of use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension

shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft.

- 13. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units.
- 14. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self-closers. (Over 3 stories in height requirements for fire rating is two (2) hours.)
- 15. The boiler shall be protected by enclosing with (1) hour fire-rated construction including fire doors and ceiling, or by providing automatic extinguishment.

- 16. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 19, 920.3.2 (BOCA National Building Code/1996), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):
 - In the immediate vicinity of bedrooms
 - In all bedrooms
 - In each story within a dwelling unit, including basements

In addition to the required AC primary power source, required smoke detectors in occupancies in Use Groups R-2, R-3 and I-1 shall receive power from a battery when the AC primary power source is interrupted. (Interconnection is required)

- 17. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type.
- 18. The Fire Alarm System shall be maintained to NFPA #72 Standard.
- 19. The Sprinkler System shall maintained to NFPA #13 Standard.

20. All exit signs, lights, and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023, & 1024. Of the City's building code. (The BOCA National Building Code/1996)

21. Section 25-135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".

22. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification to the Division of Inspection Services.

23. Ventilation shall meet the requirements of Chapter 12 Sections 1210. Of the City's Building Code. (crawl spaces & attics)

24. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade.

25. All requirements must be met before a final Certificate of Occupancy is issued.

26. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code. (The BOCA National Building Code/1996).

27. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical Code (The BOCA National Mechanical Code/1993).

28. Please read and implement the attached Land Use-Zoning report requirements.

29. The proposed Foundation & piers shall be a minimum of 4' below grade resting on Footing.

30. The piers shall have a fastening device between pier and framing member to stop movement.

B. Samuel Horvics, Building Inspector

cc: Lt. McDougall, PFD
Marge Schmuckai

THIS IS NOT A PERMIT/CONSTRUCTION CANNOT COMMENCE UNTIL THE PERMIT IS ISSUED

**Building or Use Permit Pre-Application
Additions/Alterations/Accessory Structures
To Detached Single Family Dwelling**

In the interest of processing your application in the quickest possible manner, please complete the Information below for a Building or Use Permit.

NOTEIf you or the property owner owes real estate or personal property taxes or user charges on any property within the City, payment arrangements must be made before permits of any kind are accepted.**

Location/Address of Construction: <u>Little Diamond I.</u>			
Tax Assessor's Chart, Block & Lot Number #001		Owner:	Telephone#:
Chart# <u>105</u>	Block# <u>Y</u>	Lot# <u>12,13,19</u>	<u>Linda G. Ann Plum</u>
Owner's Address: <u>1413 Center Cross Church Rd. Asheboro, NC 27203</u>		Lessee/Buyer's Name (If Applicable)	Cost Of Work: Fee
			<u>\$2500.00</u> <u>\$35</u>
Proposed Project Description:(Please be as specific as possible)			
<u>Screened in porch with storage area</u>			
Contractor's Name, Address & Telephone		Rec'd By:	
<u>Self</u>		<u>MM</u>	

Separate permits are required for Internal & External Plumbing, HVAC and Electrical installation.

- All construction must be conducted in compliance with the 1996 B.O.C.A. Building Code as amended by Section 6-Art II.
- All plumbing must be conducted in compliance with the State of Maine Plumbing Code.
- All Electrical Installation must comply with the 1996 National Electrical Code as amended by Section 6-Art III.
- HVAC(Heating, Ventilation and Air Conditioning) installation must comply with the 1993 BOCA Mechanical Code.

You must include the following with you application:

- 1) A Copy of Your Deed or Purchase and Sale Agreement
- 2) A Copy of your Construction Contract, if available
- 3) A Plot Plan (Sample Attached)

If there is expansion to the structure, a complete plot plan (Site Plan) must include:

- The shape and dimension of the lot, all existing buildings (if any), the proposed structure and the distance from the actual property lines. Structures include decks porches, a bow windows cantilever sections and roof overhangs, as well as, sheds, pools, garages and any other accessory structures.
- Scale and required zoning district setbacks

4) Building Plans (Sample Attached)

A complete set of construction drawings showing all of the following elements of construction:

- Cross Sections w/Framing details (including porches, decks w/ railings, and accessory structures)
- Floor Plans & Elevations
- Window and door schedules
- Foundation plans with required drainage and dampproofing
- Electrical and plumbing layout. Mechanical drawings for any specialized equipment such as furnaces, chimneys, gas equipment, HVAC equipment (air handling) or other types of work that may require special review must be included.


Certification

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.

Signature of applicant: <u>Linda Ann Plum</u>	Date: <u>July 16, 1998</u>
---	----------------------------

Site-Review Fee: \$150.00/Building Permit Fee: \$25.00 for the 1st \$1000.cost plus \$5.00 per \$1,000.00 construction cost thereafter.

Mail TO: Linda Ann Plum
Little Diamond Island
Portland, ME 04109



Applicant: GAIL Ann Plummer

Date: 7/17/98

Address: Rockledge Ave, L.D.I

C-B-L: 105-y-12, 13, 19

CHECK-LIST AGAINST ZONING ORDINANCE

Date - Existing 1970

Zone Location - IR-2

Interior or corner lot -

Proposed Use/Work -

Sewage Disposal -

Lot Street Frontage -

Front Yard - 25' req - 35' shown

Rear Yard - 25' req - 85'+ shown

Side Yard - 20' req - 58' shown

Projections -

Width of Lot -

Height - 1 story

Lot Area -

20,374 sq ft

Lot Coverage/ Impervious Surface -

Area per Family -

Off-street Parking -

Loading Bays -


Site Plan - N/A

Shoreland Zoning/ Stream Protection -

within 250' of HWM
but 85'+ from HWM

Flood Plains - on map 14


PLOT PLAN
SEASERS LOTS 105 Y 12, 13, 19



BUILDING PERMIT APPLICATION
FOR PORCH ADDITION TO EXISTING
STRUCTURE


L. W. EGAN ARCH PLUM
JULY 1998

SHEET 2 of 9



SCALE 1/8" = 1'

BUILDING PERMIT APPLICATION
 FOR PORCH ADDITION
 2 W 3' GALV ANV PLUM
 WEST 5' SOUTH ELEVATIONS



SCALE 1/8" = 1'

WENDELL S GAIL ANN PLUM
 ROCKLEDGE AVE
 LITTLE HARMOND ISLAND
 LOTS 105, 12-13-19

SHEET 1 OF 4

FOUNDATION:
CONCRETE PIERS 8' OC w/ REBAR

DECK FRAMING:
4" X 8" HEMLOCK SILLS & BEAM
2" X 8" JOIST 16" OC

ROOF FRAMING:
2 X 8" RAFTERS 16" OC
RIDGE BEAM 4" X 8", SUPPORTED BY PARTITION

SPAN }

WALL FRAMING:
2 X 4" - 16" OC, 4" X 4" POSTS 4' OR LESS... O.C

SHEATHING TO BE 1" X FIVE

ROOF TO BE ROLL ROOFING TO MATCH EXISTING

BUILDING PERMIT APPLICATION
FOR PORCH ADDITION
L W & GAIL ANN PLUM

FOUNDATION & STRUCTURE

SHEET 9 OF 9

PLUMBING APPLICATION

Department of Human Sciences
Division of Health Engineering

105-2-003

PROPERTY ADDRESS

Town or
Plantation

LDI - Portland

Street
Subdivision Lot #

77 Rockledge

PROPERTY OWNERS NAME

Last:

Davis

First:

Arden

Applicant
Name:

Darling Plumbing & Heating Inc

Mailing Address of
Owner/Applicant
(If Different)

27 Unimac Ave
Portland ME 04103

PORTLAND 7712 TOWN COPY
Date Permit Issued: 5,25,01 \$ 172.99 Double Fee Charged
L.P.I. # 0124
Local Plumbing Inspector Signature

105-2-003

Owner/Applicant Statement

I certify that the information submitted is correct to the best of my knowledge and understand that any falsification is reason for the Local Plumbing Inspectors to deny a Permit.

Signature of Owner/Applicant

Date

Caution: Inspection Required

I have inspected the installation authorized above and found it to be in compliance with the Maine Plumbing Rules.

Local Plumbing Inspector Signature

Date Approved

PERMIT INFORMATION

This Application is for

- NEW PLUMBING
- RELOCATED PLUMBING

Type of Structure To Be Served:

- SINGLE FAMILY DWELLING
- MODULAR OR MOBILE HOME
- MULTIPLE FAMILY DWELLING
- OTHER - SPECIFY _____

Plumbing To Be Installed By:

- MASTER PLUMBER
- OIL BURNERMAN
- MFG'D. HOUSING DEALER/MECHANIC
- PUBLIC UTILITY EMPLOYEE
- PROPERTY OWNER

LICENSE # 97160

Hook-Up & Piping Relocation Maximum of 1 Hook-Up	Number	Column 2 Type of Fixture	Number	Column 1 Type of Fixture
HOOK-UP: to public sewer in those cases where the connection is not regulated and inspected by the local Sanitary District.	01	Hosebibb / Sillcock	1	Bathtub (and Shower)
		Floor Drain	0,2	Shower (Separate)
OR		Urinal	0,1	Sink
		Drinking Fountain	0,2	Wash Basin
HOOK-UP: to an existing subsurface wastewater disposal system.		Indirect Waste	0,2	Water Closet (Toilet)
		Water Treatment Softener, Filter, etc.	0,1	Clothes Washer
OR		Grease / Oil Separator	0,1	Dish Washer
		Dental Cuspidor	0,1	Garbage Disposal
PIPING RELOCATION: of sanitary lines, drains, and piping without new fixtures.		Bidet	1	Laundry Tub
		Other: _____	0,1	Water Heater
TRANSFER FEE [\$6.00]		Fixtures (Subtotal) Column 2	11	Fixtures (Subtotal) Column 1
			0,1	Fixtures (Subtotal) Column 2
SEE PERMIT FEE SCHEDULE FOR CALCULATING FEE				
			21	Total Fixtures
				Fixture Fee
				Transfer Fee
				Hook-Up & Relocation Fee
			72.00	Permit Fee (Total)

ELECTRICAL PERMIT

City of Portland, Me.



15268

To the Chief Electrical Inspector, Portland Maine:
 The undersigned hereby applies for a permit to make electrical installations
 in accordance with the laws of Maine, the City of Portland Electrical Ordinance,
 National Electrical Code and the following specifications:

Date 4/19/01
 Permit # 1424
 CBL# 1052003 1052003

LOCATION: 77 Rock ledge Ave Little Diamond ±
 METER MAKE & # _____
 OWNER Arden Davis
 PHONE # 799-1936

							TOTAL EACH FEE			
OUTLETS	50	Receptacles	20	Switches	6	Smoke Detector		.20	15.20	
FIXTURES	20	Incandescent		Fluorescent		Strips		.20		
SERVICES	X	Overhead		Underground		TTL AMPS	200 A. -<800	15.00	15.00	
		Overhead		Underground			>800	25.00		
Temporary Service		Overhead		Underground		TTL AMPS		25.00		
METERS	①	(number of)						1.00	1.00	
MOTORS		(number of)						2.00		
RESID/COM		Electric units						1.00		
HEATING		oil/gas units		Interior		Exterior		5.00		
APPLIANCES	①	Ranges		Cook Tops		Wall Ovens		2.00	2.00	
		Insta-Hot	①	Water heaters		Fans		2.00	2.00	
	②	Dryers	①	Disposals	①	Dishwasher		2.00	6.00	
		Compactors		Spa	①	Washing Machine		2.00	2.00	
		Others (denote)						2.00		
MISC. (number of)		Air Cond/win						3.00		
		Air Cond/cent				Pools		10.00		
		HVAC		EMS		Thermostat		5.00		
		Signs						10.00		
		Alarms/res						5.00		
		Alarms/com						15.00		
		Heavy Duty(CRKT)						2.00		
		Circus/Carnv						25.00		
		Alterations						5.00		
		Fire Repairs						15.00		
		E Lights						1.00		
		E Generators						20.00		
PANELS		Service		Remote	②	Main		4.00	4.00	
TRANSFORMER		0-25 Kva						5.00		
		25-200 Kva						8.00		
		Over 200 Kva						10.00		
							TOTAL AMOUNT DUE			
MINIMUM FEE/COMMERCIAL 45.00							MINIMUM FEE	35.00	49.20	

INSPECTION: Will be ready or will call _____

CONTRACTORS NAME P.A. Iapalitano MASTER LIC. # 7765
 ADDRESS _____ LIMITED LIC. # _____
 TELEPHONE _____
 SIGNATURE OF CONTRACTOR P.A. Iapalitano