

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

GIESELMAN GEORGE H & JANE JTS /JASON RYAN

Located at

174 WHITEHEAD AVE, Cushings Island

PERMIT ID: 2013-00898

ISSUE DATE: 06/07/2013

CBL: 106C A024001

has permission to **Enclose existing second floor deck (130 sf)**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Jon Rioux

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

Single family

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing
Electrical - Residential
Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-00898	Date Applied For: 05/03/2013	CBL: 106C A024001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Single Family	Proposed Project Description: Enclose existing second floor deck (130 sf)			
<p>Dept: Zoning Status: Approved w/Conditions Reviewer: Ann Machado Approval Date: 05/14/2013</p> <p>Note: Site plan shows that the existing building meets the setbacks and that it is located 162' from the high water mark. Ok to Issue: <input checked="" type="checkbox"/></p> <p>Conditions:</p> <p>1) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.</p> <p>2) This property shall remain a single family dwelling. Any change of use shall require a separate permit application for review and approval.</p>				
<p>Dept: Building Status: Approved w/Conditions Reviewer: Jon Rioux Approval Date: 06/05/2013</p> <p>Note: Ok to Issue: <input checked="" type="checkbox"/></p> <p>Conditions:</p> <p>1) See the condition(s) below for any change (additions or enlargement) to the existing bedrooms.</p> <p>A code compliant emergency escape shall be provided the renovated bedroom. Window sills in locations more than 72 inches from finished grade shall be a minimum of 24 inches (no higher than 44 inches) above the finished floor of the room, or in compliance with Section R612.4.2</p> <p>R612.2 Window sills. In dwelling units, where the opening of an operable window is located more than 72 inches above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4 inch diameter sphere where such openings are located within 24 inches of the finished floor.</p> <p>2) Hardwired (non- ionization detection technology) interconnected battery backup smoke alarms shall be installed in each bedroom, protecting the bedrooms, and on every level.</p> <p>A field inspection will verify your current smoke detector arrangement and the City's minimal code requirements.</p> <p>R315.2 Where required in existing dwellings. Where work requiring a permit occurs in existing dwellings that have attached garages or in existing dwellings within which fuel-fired appliances exist, carbon monoxide alarms shall be provided in accordance with Section R315.1.</p> <p>3) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.</p> <p>4) Ventilation of this space is required per ASRAE 62.2 , 2007 edition.</p> <p>For conditioned space- insulation shall comply with the IECC, 2009 (Maine State Energy Codes).</p> <p>5) Provide appropriate hanger at ridge connection.</p>				