Date: 10/07/16

CUPOLA

WINDOW SEAT
CROSS SECTION

TYPICAL CROSS SECTION

FIRST FLOOR

SECOND FLOOR

NOTE:

THE HOUSE WILL BE HEATED BY A SINGLE ELECTRIC HEAT PUMP UNIT. THEREFORE, VENTING FOR THE HEATING SYSTEM WILL NOT BE NECESSARY.

WINDOW SCHEDULE

MARK	QTY	ROUGH OPENING	NOTES
A	9	2-8X4-0	CASEMENT
B	2	5-0X4-0	FIXED FRAME
C	2	6-0X1-2	TRANSOME
D	3	3-0X2-0	AWNING
E	1	2-0X4-0 (3)	3 WAY
F	1	6-0X4-0	FIXED FRAME
G	3	3-0X2-6	AWNING
H	4	4-0X2-6	AWNING

DOOR SCHEDULE

MARK	QTY	SIZE	NOTES
1	1	3-0 X 6-8	SOLID EXT.
2		3-0 X 6-8	INTERIOR BARN
3	2	6-0 X 6-8	12LITE FRENCH EXT
4	2	3-0 X 6-8	INTERIOR POCKET
5	3	3-0 X 6-8	INTERIOR
6	1	3-0 X 6-6	COLONIAL EXT
7	1	6-0 X 6-6	12LITE FRENCH EXT

1/4" = 1'-0"
GRAPHIC SCALE

0 4 8 12 16 (FEET)

NO.	DESCRIPTION	DATE
C.	PERMITTING AND INSPECTIONS COMMENTS	10/06/16
B.	PERMITTING AND INSPECTIONS CLARIFICATION	10/01/16
A.	COMMENTS FROM BUILDING INSPECTIONS	09/20/16

REVISIONS

FLOOR PLAN
SOUTH SIDE, LLC.
87 CHURCH ROAD

FOR: SOUTH SIDE, LLC.
243 JENNIE LANE
ELIOT MAINE, 03903

SCALE: 1/4" = 1'	APPROVED BY:	DRAWN BY: BRW
DATE: 07/10/2016		REVISION : DATE 10/06/16
JOB NO: XXXX-XX	CAD FILE:	SHEET 3 OF 3