Inspections Division
Date: 02/04/16

LETTER OF TRANSMITTAL

Date: February 1, 2016

From: Jim Robinson Master Oil Burner Technician
Mainely Plumbing and Heating
674 Main Street
Gorham, Maine 04038

To: City of Portland
Inspection department

We are doing an emergency steam boiler replacement at 103 Deerfield Rd Portland, Me.
We have sized the boiler based on the steam radiation as needed and will be installing a new Weil McLain SGO-4 steam boiler with electronic LWCO and water feed valve.
Total sq ft of steam needed to make the system perform 430 sq ft of steam.
We will also be installing a new 7" SS chimney liner as required on an unlined chimney.
The boiler will be installed in the same location as the existing boiler in the basement.
We will also be installing a sprinkler heat over each of the boilers.
System will be installed to the State of Maine Codes.

Jim Robinson, President
Master Oil, Gas & Plumbing Technician
Mainely Plumbing and Heating Inc.
674 Main St.
Gorham, Maine 04038
207-854-4969
Serving the Community for over 29 years
PHCC Member for over 24 years