



XDG-P115-H05 CONSTRUCTION FEATURES AND ACCESSORIES

Unit Overview

Model	Airflow (CFM)	Heating	Cooling	Electrical V/C/P
XDG-P115-H05	1,604	Direct Gas	No Cooling	208/60/3

Features

- Exterior housing constructed of galvanized steel
- Removable access panels
- Painted or galvanized steel blower and bearing supports
- Direct-drive backward curved supply blower
- Fan assembly is mounted on neoprene vibration isolators
- Corrosion resistant fasteners are standard
- Disconnect mounted by factory

Options and Accessories

- Air Flow Arrangement: Variable Volume
- Aluminum Mesh Weatherhood
- Damper: Inlet
- Outdoor Air Intake Position: End
- Discharge Position: Bottom
- Coating: Galvanized
- Insulation: Duct Liner - Heat Source On
- Access Side: Right-Hand
- Control Center
- Heat Inlet Air Sensor
- External Cooling Lockout Relay
- Mounting: GPI-21/55.5-G12
- Curb Includes: 1 in. Insul.
- Unit Warranty: 1 Yr (Standard)



NOTES:

Integral unit disconnect is supplied as a standard.

Unit weight does NOT include skid/crating and may vary by 15% based on selected options.