



Model: XRUB-180HP-7

Belt Drive Upblast Centrifugal Roof Exhaust Fan

Standard Construction Features:

- Aluminum housing - Backward inclined aluminum wheel - Curb cap with prepunched mounting holes - Motor and drives isolated on shock mounts - Drain trough - Ball bearing motors - Adjustable motor pulley - Adjustable motor plate - Fan shaft mounted in ball bearing pillow blocks - Bearings meet or exceed temperature rating of fan - Static resistant belts - Corrosion resistant fasteners - Internal lifting lugs

Selected Options & Accessories:

- High Efficient Motor - meets Larkin High Efficiency Table
- Motor VFD Rated without Shaft Grounding Protection
- UL/cUL 762 Listed - "Power Ventilators for Rest. Exh. Appliances"
- Switch, NEMA-3R, Toggle, Shipped with Unit
- Junction Box Mounted & Wired
- Roof Curb-Galv., GPI-30-G12, Under Sized 1.5 in. Total
- Curb Extension-Galv., VCE-30-G11
- Hinged Bracket Kit (PN 878105) (Shipped Loose)
- Grease Trap (PN 475538)
- Heat Baffle (Attached)
- Bearings with Grease Fittings, L10 life of 100,000 hrs (L50 avg. life 500,000 hrs)