



Direct Gas Heating

Heating Type	Gas Type	Input (MBH)	Output (MBH)	LAT (F)	Temp. Rise (F)
Direct Gas	Natural	132.4	121.8	70.0	70.0

Direct Gas Unit Details

This unit will come equipped with the following:

- 92% efficiency
- Pilot Ignition
- High quality cast aluminum burners with stainless steel mixing plates
- Burner capable of 30:1 turndown
- Maxitrol electronic modulation burner control

Heating Details

Agency Approval	ETL and IRI
Building Gas Pressure	1/2 PSI
Temperature Control	Discharge
Units Rated Gas Pressure	1/2 PSI
Ignition Control	Pilot
Flame Sensing	FlameRod
External Gas Regulator	No
Min Gas Pressure For Maximum Fire	7 in. wg