



GROUND FLOOR CEILING
GENERAL NOTES:

1. NEW 1 HR. RATED SUSPENDED CEILING SYSTEM TYPICAL AT GROUND FLOOR.
2. MAINTAIN EXISTING GRILLE PATTERN TO ALLOW MECHANICAL SUPPLY AND RETURN RE-CONNECTION.
3. EXISTING RECESSED CAN FIXTURES - REPLACED WITH NEW 2 X 2
4. REMOVE ALL EXISTING CEILING HARDWARE COMPLETELY.

LIGHTING / CEILING
SYMBOLS

- NEW SURFACE MOUNTED 24"x24" LED CEILING LIGHT
- NEW SURFACE MOUNTED 24"x24" LED CEILING LIGHT W/ EMERGENCY LIGHTING OPTION
- NEW SURFACE MOUNTED 24"x24" LED CEILING LIGHT
- 48" SURFACE UTILITY LIGHT
- PENDANT LIGHT FIXTURE - NOT USED
- RECESSED CAN TO BE REMOVED & REPLACED
- ASSUMED SUPPLY
- ASSUMED RETURN
- EXISTING SPRINKLER HEAD TO REMAIN IN EXISTING LOCATION - PROTECT DURING CONSTRUCTION

1 FIRST FLOOR REFLECTED CEILING PLAN
A.1.4 SCALE: 3/16" = 1'-0"

PROGRESS SET - NOT FOR CONSTRUCTION

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF WHIPPLE CALLENDER ARCHITECTS. IT SHALL NOT BE USED FOR ANY OTHER PURPOSE THAT FOR WHICH IT IS SPECIFICALLY FURNISHED.