


CONCEPT DRAWING FOR FREESTANDING D.F. SIGN



CABINET & METAL FACE: \_\_\_\_\_ TO BEST MATCH BUILDING MATERIALS  
 4'-0" X 8'-3" INTERNALLY ILLUMINATED SIGN CABINET  
 COPY IS FACE LIT & HALO LIT  
 COPY JIGGED OUT  
 BACKED UP AND PUSH THRU WITH 3/4" ISLAND CUT CLEAR ACRYLIC  
 (WHITE DIFFUSER FILM ON SECOND SURFACE)  
 COPY FACES WITH RESPECTIVE TRANS. VINYL

2'-5" X 8'-3" EMC - FULL COLOR

3'-9" X 8'-3" POLE WRAP PAINTED ALUMINUM

VECTOR ART ON FILE IN DESIGN

 PMS 107 C  
 3M TRANS. LIGHT LEMON YELLOW VINYL  
 UPDATE NAME 6/12/15

 PMS 186 C  
 3M TRANS. RED VINYL

3M TRANS. SILVER GREY VINYL OUTLINE TO LOGO



www.baileysign.com  
 9 Thomas Drive  
 Col. Westbrook Executive Park  
 Westbrook, ME 04092  
 207-774-2843 / 1-800-539-SIGN  
 Fax: 774-1193  
 E-Mail: sales@baileysign.com

**PLEASE NOTE:**  
 THIS IS A PROGRESS PRINT - FIELD MEASUREMENTS MAY  
 OR MAY NOT NEED TO BE VERIFIED.

THIS DESIGN IS THE EXCLUSIVE PROPERTY OF BAILEY SIGN  
 INCORPORATED AND ALL RIGHTS TO ITS USE OR REPRO-  
 DUCATION ARE RESERVED.

THE ACCURACY OF THIS COLOR RENDERING IS LIMITED BY MEDIA  
 AND OUTPUT DEVICES AND IS INTENDED FOR REPRESENTATIONAL USE  
 ONLY. ACTUAL MANUFACTURING/GRAPHIC COLORS ALSO VARY  
 DEPENDING ON PROCESSES & MATERIALS USED. 100% COLOR MATCHES  
 OF SUBMITTED SPECIFICATIONS CAN NOT BE GUARANTEED.

IF AN ELECTRIC SIGN, THEN INSTALLATION MUST BE ACCOMPLISHED  
 IN TOTAL COMPLIANCE WITH ARTICLE 600 OF THE NATIONAL  
 ELECTRIC CODE, THE REQUIREMENTS OF UNDERWRITERS LABORATORY,  
 CANADIAN STANDARDS ASSOCIATION AND/OR ANY APPLICABLE  
 LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING  
 OF THE SIGN

ALL ELECTRICAL SIGNS REQUIRE ROUTINE MAINTENANCE.

**VOLTAGE**

**APPROVAL**

CLIENT

APPROVED \_\_\_\_\_ DATE \_\_\_\_\_

BAILEY SIGN REPRESENTATIVE

APPROVED \_\_\_\_\_ DATE \_\_\_\_\_

**DESIGNATED COPY FOR:**



ESTIMATING/OUTSOURCING

GRAPHICS

FABRICATION

ROUTER

PAINT

INSTALLATION

CUSTOMER / SIGN LOCATION

INFINITY FEDERAL CREDIT UNION

29 BAXTER BOULEVARD  
 PORTLAND, MAINE

SALESPERSON: DE DRAWN BY: LWM

PS # D-047 W.C. #

SCALE 1/2" = 1' DATE 12/14/16

REVISION # / DATE / NOTES / INITIALS

DRAWING #

07758 A

SHEET \_\_\_\_\_ OF \_\_\_\_\_

REF. DR. \_\_\_\_\_