

SECTION 07841 - THROUGH-PENETRATION FIRESTOP SYSTEMS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.02 SUMMARY

- A. This Section includes through-penetration firestop systems for penetrations through the following fire-resistance-rated assemblies, including both empty openings and openings containing penetrating items:
 - 1. Floors.
 - 2. Ceilings.
 - 3. Walls and partitions.
- B. Related Sections include the following:
 - 1. Division 7 Section "Building Envelope Air Sealing".
 - 2. Division 9 Section "Gypsum Board Assemblies" for firestopping where fire rated gypsum board assemblies butting adjacent construction.
 - 3. Division 15 Sections specifying duct and piping penetrations.
 - 4. Division 16 Sections specifying cable and conduit penetrations.

1.03 PERFORMANCE REQUIREMENTS

- A. General: For the following constructions, provide through-penetration firestop systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assembly penetrated.
 - 1. Fire-resistance-rated non-load-bearing walls, including partitions, with fire-protection-rated openings.
 - 2. Fire-resistance-rated floor assemblies.
 - 3. Fire-resistance-rated ceiling assemblies.
- B. F-Rated Systems: Provide through-penetration firestop systems with F-ratings indicated, as determined per ASTM E 814, but not less than that equaling or exceeding fire-resistance rating of constructions penetrated.
- C. T-Rated Systems: For the following conditions, provide through-penetration firestop systems with T-ratings indicated, as well as F-ratings, as determined per ASTM E 814, where systems protect penetrating items exposed to potential contact with adjacent materials in occupiable floor areas:
 - 1. Penetrations located outside wall cavities.
 - 2. Penetrations located outside fire-resistive shaft enclosures.
 - 3. Penetrations located in construction containing fire-protection-rated openings.
 - 4. Penetrating items larger than 4-inch- diameter nominal pipe or 16 sq. in. in overall cross-sectional area.

- D. For through-penetration firestop systems exposed to view, traffic, moisture, and physical damage, provide products that after curing do not deteriorate when exposed to these conditions both during and after construction.
 - 1. For piping penetrations for plumbing and wet-pipe sprinkler systems, provide moisture-resistant through-penetration firestop systems.
 - 2. For floor penetrations with annular spaces exceeding 4 inches in width and exposed to possible loading and traffic, provide firestop systems capable of supporting floor loads involved either by installing floor plates or by other means.
 - 3. For penetrations involving insulated piping, provide through-penetration firestop systems not requiring removal of insulation.
 - 4. Products in public areas shall be paintable.
- E. For through-penetration firestop systems exposed to view, provide products with flame-spread ratings of less than 25 and smoke-developed ratings of less than 450, as determined per ASTM E 84.
- F. Fire-Resistive Joint Sealants: Provide joint sealants with fire-resistance ratings indicated, as determined per UL 2079, but not less than that equaling or exceeding fire-resistance rating of construction in which joint occurs. Comply with LEED low emitting materials - adhesives and sealants.

1.04 SUBMITTALS

- A. General: Submit in accordance with Section 01330.
- B. Product Data: For each type of through-penetration firestop system product indicated. List product characteristics, typical uses, performance and limitation criteria, and test data.
 - 1. Include manufacturer's installation instructions for each product.
- C. Shop Drawings: For each through-penetration firestop system, show each kind of construction condition penetrated, relationships to adjoining construction, and kind of penetrating item. Indicate which firestop materials will be used where and thickness for different hourly ratings. Include firestop design designation of testing and inspecting agency acceptable to authorities having jurisdiction that evidences compliance with requirements for each condition indicated.
 - 1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each through-penetration firestop system configuration for construction and penetrating items.
 - 2. Where Project conditions require modification of qualified testing and inspecting agency's illustration to suit a particular through-penetration firestop condition, submit illustration, with modifications marked, approved by through-penetration firestop system manufacturer's fire-protection engineer.
 - 3. For those firestop applications that exist for which no UL tested system is available through manufacturer, manufacturer's engineering judgement derived from a similar UL system design or other tests shall be submitted to local authorities having jurisdiction for their review and approval prior to installation. Manufacturer's engineering judgement shall follow requirements set forth by the International Firestop Council.
- D. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project

names and addresses, names and addresses of architects and owners, and other information specified.

- E. Product Certificates: Signed by manufacturers of through-penetration firestop system products certifying that products furnished comply with requirements.
- F. Product Test Reports: From an independent qualified testing agency indicating through-penetration firestop system complies with requirements, based on comprehensive testing of current products.

1.05 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is qualified by having the necessary experience, staff, and training to install manufacturer's products per specified requirements. A manufacturer's willingness to sell its through-penetration firestop system products to Contractor or to an installer engaged by Contractor does not in itself confer qualification on buyer.
- B. Source Limitations: Obtain through-penetration firestop systems, for each kind of penetration and construction condition indicated, from a single manufacturer.
- C. Fire-Test-Response Characteristics: Provide through-penetration firestop systems that comply with the following requirements and those specified in "Performance Requirements" Article:
 - 1. Firestopping tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL, Warnock Hersey, or another agency performing testing and follow-up inspection services for firestop systems acceptable to authorities having jurisdiction.
 - 2. Through-penetration firestop systems are identical to those tested per ASTM E 814. Provide rated systems complying with the following requirements:
 - a. Through-penetration firestop system products bear classification marking of qualified testing and inspecting agency.
 - b. Through-penetration firestop systems correspond to those indicated by reference to through-penetration firestop system designations listed by UL in "Fire Resistance Directory."
- D. Provide through-penetration firestop system products containing no detectable asbestos as determined by the method specified in 40 CFR Part 763, subpart F, Appendix A, Section 1, "Polarized Light Microscopy. "
- E. Field-Testing: Each type of through-penetration firestop system shall be field-tested.
- F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Deliver through-penetration firestop system products to Project site in original, unopened containers or packages with intact and legible manufacturers' labels identifying product and manufacturer; date of manufacture; lot number; shelf life, if applicable; qualified testing and inspecting agency's classification marking applicable to Project; curing time; and mixing instructions for multi-component materials.

- B. Store and handle materials for through-penetration firestop systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

1.07 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install through-penetration firestop systems when ambient or substrate temperatures are outside limits permitted by through-penetration firestop system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.
- B. Ventilate through-penetration firestop systems per manufacturer's written instructions by natural means or, where this is inadequate, forced-air circulation.

1.08 COORDINATION

- A. Coordinate Work of this Section with the work of other trades to assure the proper sequencing of each installation and to provide a smoke- and fire-resistant installation.
- B. Coordinate construction of openings and penetrating items to ensure that through-penetration firestop systems are installed according to specified requirements.
- C. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate through-penetration firestop systems.
- D. Notify Owner's inspecting agency at least seven days in advance of through-penetration firestop system installations; confirm dates and times on days preceding each series of installations.
- E. Do not cover up through-penetration firestop system installations that will become concealed behind other construction until Owner's inspecting agency and building inspector, if required by authorities having jurisdiction, have examined each installation.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Bio Fireshield, Carlisle, MA.
 2. W. R. Grace & Co., Construction Products Division.
 3. Hilti Construction Chemicals, Inc.
 4. Isolatek International.
 5. Nelson Firestop Products.
 6. Specified Technologies Inc.
 7. 3M Fire Protection Products.

2.02 FIRESTOPPING, GENERAL

- A. Firestop Systems: All through-penetration firestop products and systems shall be designed and installed so the basic sealing system will allow the full restoration of thermal and fire-resistance

properties of the barrier being penetrated with minimal repair if penetrants are subsequently removed.

1. Provide paintable through-penetration firestop products at locations exposed to the public. Mechanical, electrical and elevator machine rooms are not considered public spaces.
- B. Compatibility: Provide through-penetration firestop systems that are compatible with one another, with the substrates forming openings, and with the items, if any, penetrating through-penetration firestop systems, under conditions of service and application, as demonstrated by through-penetration firestop system manufacturer based on testing and field experience.
- C. Accessories: Provide components for each through-penetration firestop system that are needed to install fill materials and to comply with "Performance Requirements" Article. Use only components specified by through-penetration firestop system manufacturer and approved by the qualified testing and inspecting agency for firestop systems indicated. Accessories include, but are not limited to, the following items:
1. Permanent forming/damming/backing materials, including the following:
 - a. Slag-/rock-wool-fiber insulation.
 - b. Sealants used in combination with other forming/damming/backing materials to prevent leakage of fill materials in liquid state.
 - c. Fire-rated form board.
 - d. Fillers for sealants.
 2. Temporary forming materials.
 3. Substrate primers.
 4. Collars.
 5. Steel sleeves.

2.03 FILL MATERIALS -ADHESIVES AND SEALANTS

- A. General: Provide through-penetration firestop systems containing the types of fill materials indicated in the Through-Penetration Firestop System Schedule at the end of Part 3 by reference to the types of materials described in this Article. Fill materials are those referred to in directories of the referenced testing and inspecting agencies as fill, void, or cavity materials.
- B. Cast-in-Place Firestop Devices: Factory-assembled devices for use in cast-in-place concrete floors and consisting of an outer metallic sleeve lined with an intumescent strip, a radial extended flange attached to one end of the sleeve for fastening to concrete formwork, and a neoprene gasket.
1. Product:
 - a. CP 680 Cast-In-Place Firestop Device; Hilti Construction Chemicals, Inc.
- C. Latex Sealants: Single-component latex formulations that after cure do not re-emulsify during exposure to moisture.
1. Products:
 - a. Biostop 500+ Intumescent Firestop; Bio Fireshield.
 - b. FlameSafe FS900 Sealant; W. R. Grace & Co.
 - c. Fire Barrier CP 25WB+; 3M Fire Protection Products.
 - d. SpecSeal LC 150 Sealant; Specified Technologies Inc.

- D. Firestop Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.
1. Products:
 - a. Biostop Pipe Collar; Bio Fireshield.
 - b. FlameSafe FSWS Series FlameSafe Devices; W. R. Grace & Co.
 - c. CP 642 and CP 643 Firestop Jacket; Hilti Construction Chemicals, Inc.
 - d. SpecSeal Series LCC and Series SSC Firestop Collars; Specified Technologies Inc.
- E. Intumescent Composite Sheets: Rigid panels consisting of aluminum-foil-faced elastomeric sheet bonded to galvanized steel sheet.
1. Products:
 - a. Biostop Composite Sheet; Bio Fireshield.
 - b. CS-195_ Composite Sheet; 3M Fire Protection Products.
- F. Intumescent Putties: Nonhardening dielectric, water-resistant putties containing no solvents, inorganic fibers, or silicone compounds.
1. Products:
 - a. FlameSafe FSP 1000 Putty and FSP 1077 Putty Pads; W. R. Grace & Co.
 - b. CP 617 and CP 618 Putty Pads and Putty Sticks; Hilti Construction Chemicals, Inc.
 - c. MPS-2 Moldable Putty Stix and Putty Pads; 3M Fire Protection Products.
 - d. Spec-Seal Firestop Putty Bars and Putty Pads; Specified Technologies Inc.
- G. Intumescent Wrap Strips with Foil: Single-component intumescent elastomeric sheets with aluminum foil on one side.
1. Products:
 - a. CP 645 Wrap Strips; Hilti Construction Chemicals, Inc.
 - b. Fire Barrier FS-195+ Wrap Strip; 3M Fire Protection Products.
- H. Intumescent Wrap Strips: Single-component intumescent elastomeric sheets.
1. Products:
 - a. Biostop Wrap Strip; Bio Fireshield.
 - b. SpecSeal Series SSWBLU and Series SSWRED Intumescent Wrap; Specified Technologies Inc.
- I. Mortars: Prepackaged, dry mixes consisting of a blend of inorganic binders, hydraulic cement, fillers, and lightweight aggregate formulated for mixing with water at Project site to form a non-shrinking, homogeneous mortar.
1. Products:
 - a. FlameSafe Mortar Safe; W. R. Grace & Co.
 - b. CP 636 Firestop Mortar; Hilti Construction Chemicals, Inc.
 - c. SpecSeal Firestop Mortar; Specified Technologies Inc.
- J. Pillows/Bags: Reusable, heat-expanding pillows/bags consisting of glass-fiber cloth cases filled with a combination of mineral-fiber, water-insoluble expansion agents and fire-retardant additives.
1. Products:
 - a. Bio Firestop Pillows; Bio Fireshield.
 - b. FlameSafe Bags and FlameSafe Pillows; W. R. Grace & Co.
 - c. CP 651 Firestop Cushion; Hilti Construction Chemicals, Inc.
 - d. SpecSeal Firestop Pillows; Specified Technologies Inc.

- K. Silicone Foams: Multi-component, silicone-based liquid elastomer that, when mixed, expand and cure in place to produce a flexible, non-shrinking foam.
1. Products:
 - a. CP 620 Firestop Foam; Hilti Construction Chemicals, Inc.
 - b. Fire Barrier 2001 Silicone RTV Foam; 3M Fire Protection Products.
 - c. SpecSeal Pen 200 Silicone Foam; Specified Technologies Inc.
- L. Silicone Sealants: Moisture-curing, single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below:
1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces and nonsag formulation for openings in vertical and other surfaces requiring a nonslumping, gunnable sealant, unless indicated firestop system limits use to nonsag grade for both opening conditions.
 - a. Products:
 - 1) Biotherm 200SL Firestop Sealant; Bio Fireshield.
 - 2) CP 604 Self-Leveling Firestop Sealant; Hilti Construction Chemicals, Inc.
 - 3) Fire Barrier 1003SL; 3M Fire Protection Products.
 - 4) SpecSeal Pen 300 Silicone Sealant; Specified Technologies Inc.
 2. Grade for Horizontal Surfaces: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces.
 - a. Products:
 - 1) Biotherm 200SL Firestop Sealant; Bio Fireshield.
 - 2) CP 604 Self-Leveling Firestop Sealant; Hilti Construction Chemicals, Inc.
 - 3) Fire Barrier 1003SL; 3M Fire Protection Products.
 3. Grade for Vertical Surfaces: Nonsag formulation for openings in vertical and other surfaces.
 - a. Products:
 - 1) Biotherm 100 Firestop Sealant; Bio Fireshield.
 - 2) CP 601S Elastomeric Firestop Sealant; Hilti Construction Chemicals, Inc.
- M. Accessories: Forming/damming materials composed of mineral fiberboard or other type as recommended by through-penetration firestop systems manufacturer.

2.04 MIXING

- A. For those products requiring mixing before application, comply with through-penetration firestop system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Surface Cleaning: Clean out openings immediately before installing through-penetration firestop systems to comply with written recommendations of firestop system manufacturer and the following requirements:
 - 1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of through-penetration firestop systems.
 - 2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with through-penetration firestop systems. Remove loose particles remaining from cleaning operation.
 - 3. Remove laitance and form-release agents from concrete.
- B. Priming: Prime substrates where recommended in writing by through-penetration firestop system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.
- C. Masking Tape: Use masking tape to prevent through-penetration firestop systems from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from firestop system materials. Remove tape as soon as possible without disturbing firestop system's seal with substrates.

3.03 THROUGH-PENETRATION FIRESTOP SYSTEM INSTALLATION

- A. General: Install through-penetration firestop systems to comply with "Performance Requirements" Article and firestop system manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming/damming/backing materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
 - 1. After installing fill materials, remove combustible forming materials and other accessories not indicated as permanent components of firestop systems.
- C. Install fill materials for firestop systems by proven techniques to produce the following results:
 - 1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
 - 2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
 - 3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.04 FIELD QUALITY CONTROL

- A. Inspecting Agency: Owner may engage a qualified independent inspecting agency to inspect through-penetration firestop systems and to prepare test reports.
 - 1. Inspecting agency will state in each report whether inspected through-penetration firestop systems comply with or deviate from requirements.

- B. Allow for 3 random samples of each type of firestopping system to be inspected. Reinstall disturbed samples to comply with requirements.
- C. Proceed with enclosing through-penetration firestop systems with other construction only after inspection reports are issued.
- D. Where deficiencies are found, repair or replace through-penetration firestop systems so they comply with requirements.
- E. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.05 CLEANING AND PROTECTION

- A. Clean off excess fill materials adjacent to openings as Work progresses by methods and with cleaning materials that are approved in writing by through-penetration firestop system manufacturers and that do not damage materials in which openings occur.
- B. Provide final protection and maintain conditions during and after installation that ensure through-penetration firestop systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated through-penetration firestop systems immediately and install new materials to produce through-penetration firestop systems complying with specified requirements.

END OF SECTION 07841