FIRST FLOOR FINISH SCHEDULE															
		FLOOR			BASE	WALLS				MILLWORK			CEILING		
NUMBER	NAME	FINISH	ACCENT 1	ACCENT 2	FINISH	NORTH	EAST	SOUTH	WEST	CABINET	COUNTERTOPS	SECTION	FINISH	COMMENTS
101	VESTIBULE	EPT-1/CT-1	CT-2		WB-2A	PT-2	PT-1	PT-1	PT-2				MUC-1/ACP-1	SEAT-2 PAINT PT-3
102	WATER SERVICES	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-2				PT-2	
103	STAIR 3	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2					NOTE 2 & 4
104	ELEVATOR													
105	LOBBY	CT-2/EPT-3	CT-2	CPT-6	WB-2A	PT-1	PT-1	PT-1	PT-2	WB	SIMULATED STONE	CSB03L6	ACP-1	
106	TELLERS	CPT-5			WB-2A	PT-1	PT-1	PT-1	PT-2	WB	SIMULATED STONE	CSB03L6	ACP-1	
107	OFFICE	CPT-2	CPT-3		WB-2A	PT-1	PT-1	PT-1	PT-2				ACP-1	
108	MUC CL	CPT-3	CPT-4		WB-2A	PT-1	PT-1	PT-1	PT-2					BACKERBOARD PT-6
109	MOTHERROOM	CPT-6			WB-2A	PT-1	PT-1	PT-1	PT-2	WB	SIMULATED STONE	.125SQ	ACP-1	
110	OFFICE	CPT-2	CPT-3		WB-2A	PT-1	PT-1	PT-1	PT-2				ACP-1	
111	STAIR 2	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2					NOTE 2 & 4
SECOND FLOOR FINISH SCHEDULE														
201	ELEVATOR													
202	STAIR 3	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2					NOTE 2 & 4
203	CORRIDOR	EPT-1/CT-1			WB-2B	PT-1	PT-1	PT-1	PT-1	WB	SIMULATED STONE	.125SQ	ACP-1	SEAT-1 & 2 PAINT PT-3
204	CONFERENCE ROOM	CPT-7	CPT-3 & 6	CPT-6	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	SEAT-2 PAINT PT-2
205	RECEPTION/WAITING	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
206	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
207	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
208	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
209	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
210	STAIR 2	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2					NOTE 2 & 4
211	PRINT ROOM	CPT-5			WB-2B	PT-6	PT-6	PT-6	PT-6	WB	SIMULATED STONE	.125SQ	ACP-1	
212	MIRRS	CT-6			CT-6	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2				ACP-1	
213	MOTHERS	CT-6			CT-6	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2				ACP-1	
214	CONFERENCE ROOM	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
THIRD FLOOR FINISH SCHEDULE														
301	ELEVATOR													
302	STAIR 3	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2				ACP-1	NOTE 2 & 4
303	CORRIDOR	EPT-1/CT-1			WB-2B	PT-1	PT-1	PT-1	PT-1	WB	SIMULATED STONE	.125SQ	ACP-1	
304	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
305	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
306	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
307	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
308	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
309	OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	
310	STAIR 2	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2					NOTE 2 & 4
311	MAIN CL	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-1					
312	SUPERVISOR	CPT-7	CPT-6		WB-2B	PT-6	PT-6	PT-6	PT-6	WB	SIMULATED STONE	.125SQ	ACP-1	
313	TOILET	CT-6			CT-6	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2	CT-4/PT-2				ACP-1	
314	OPEN OFFICE	CPT-7	CPT-6	CPT-5	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	CLOSET CPT-3
315	CONFERENCE ROOM	CPT-7	CPT-3 & 6	CPT-6	WB-2B	PT-1	PT-1	PT-1	PT-1				ACP-1	CLOSET CPT-5
PENTHOUSE FLOOR FINISH SCHEDULE														
401	STAIR 2	RB/RT			WB-1C	PT-2	PT-2	PT-2	PT-2				ACP-1	NOTE 2 & 4
402	MECHANICAL AREA	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-1					
403	ELEC ROOM	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-1					BACKERBOARD PT-6
404	DATA / ELEC	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-1					BACKERBOARD PT-6
405	STORAGE	SCONC			WB-1C	PT-1	PT-1	PT-1	PT-1					

PAINT COLOR LEGEND

PT-1	PW7012	CREAMY
PT-2	PW6253	UPWARD
PT-3	PW6611	MONOCHABLE BLUE
PT-4	PW6238	BALDINE
PT-5	PW6453	GREAT GREEN
PT-6	PW6121	MOMENTUM
PT-7	PW7004	SNOWBOUND
PT-8	PW6801	BLACK BAGEL
PT-9	PW6255	SERIOUS GRAY

WALL BASE COLOR LEGEND

WB-# DENOTES PRODUCT AND LETTER T-S COLOR

A COLOR TO BE SELECTED BY ARCHITECT

B COLOR TO BE SELECTED BY ARCHITECT

C COLOR TO BE SELECTED BY ARCHITECT

GENERAL NOTES:

NOTE 1: PAINT DENOTES TUBULAR STEEL TRIM, PIPES, AND THUS

NOTE 2: ALL MAINFRAMES AND HM SUBFRAMES TO BE PAINTED PT-4

NOTE 3: ALL SITE MOBILE MEANDERS, CLADDS AND MISC. METAL EXPOSED TO NOW ON TOP SIDE OF STAIR TO BE PT-3A. ALL EXPOSED METAL UNDERSIDE OF STAIRS BETWEEN STR AVERE BTO BE PT-3.

NOTE 4: STAIR TREDS AND STAIR RISERS/TREADS TO BE SB VANDESOR BLUE. (BASED OF DESIGN SCHISSORITE)

NOTE 5: ALL TRANSITIONS BETWEEN DIFFERENT FINISHES TO OCCUR AT CENTERLINE OF THE DOOR.

NOTE 6: TRANSITION: BETWEEN CARPET AND TILE USE METAL DIVIDER STRIP ANODIZED ALUMINUM. VERIFY HEIGHT OF ABRUPT WITH CARPET AND TILE. ALIGN TOP OF BOTH FLOORING MATERIALS TO MAINTAIN A SMOOTH / FLAT TRANSITION. FURTHER SEAM COAT ON FLOOR LEVEL FOR AT LEAST 12 INCHES FOR EVEN TRANSITION.

NO.	DATE	DESCRIPTION
0	03.31.15	SCHEMATIC DESIGN

ISSUED FOR CONSTRUCTION
07.22.15

TAC Architectural Group Inc.

LICENSED ARCHITECT Daniel C. Miller No. 3617 STATE OF MAINE 07.22.15

BSB - MARGINAL WAY

PORTLAND, MAINE

PROJECT NO:	14-007
CAD DWG FILE:	AF601 FINISHES SCHEDULE & LEGEND.DWG
DRAWN BY:	####
CHK'D BY:	####
COPYRIGHT:	2015

SHEET TITLE

FINISHES SCHEDULE & LEGEND

AF601