



GENERAL NOTES:

1. SEE G1001 FOR PROJECT GENERAL NOTES.

GENERAL DEMOLITION NOTES:

1. COORDINATE EXTENT OF DEMOLITION WITH LOCATIONS OF PARTITIONS DESCRIBED ON PLANS AND WITH LOCATIONS OF FINISHES NOTED AS EXISTING TO REMAIN.
2. ANY WALL, PARTITION OR SURFACE DISTURBED BECAUSE OF NEW WORK OR DEMOLITION SHALL BE PATCHED AND FINISHED CONTINUOUSLY TO THE NEAREST CORNER UNLESS NOTED OTHERWISE, MATCH EXISTING ADJACENT CONSTRUCTION FINISHES, CONTINUITY AND FIRE RATINGS UNLESS NOTED OTHERWISE.
3. PROTECT ALL FINISHES, MATERIALS AND EQUIPMENT NOTED AS EXISTING TO REMAIN. CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ALL FINISHES, MATERIALS AND EQUIPMENT DAMAGED DURING CONSTRUCTION.
4. DIMENSIONS INDICATED ± ARE EXISTING CONDITION DIMENSIONS TO BE VERIFIED IN FIELD.

DEMOLITION KEY NOTES:

- 1 REMOVE PARTITION COMPLETE. COORDINATE WITH OWNER ABOUT SALVAGING REMOVED MATERIALS.
- 2 REMOVE/RELOCATE EXIT SIGN. SEE REFLECTED CEILING PLAN FOR NEW LOCATION.
- 3 REMOVE/RELOCATE FIRE EXTINGUISHER. SEE FLOOR PLAN FOR NEW LOCATION.
- 4 APPROXIMATE LIMITS OF SLAB REMOVAL. SAW-CUT SLAB FOR FIXTURE PLUMBING. COORDINATE W/ PLUMBING & FIXTURE MANUFACTURER'S REQUIREMENTS FOR EXACT LOCATION.



ARCHITECTURE ENGINEERING PLANNING
 SMART
 144 Fore Street/P.O. Box 618
 Portland, Maine 04104
 tel. (207) 772-3846
 fax. (207) 772-1070



PROJECT TITLE:
USM COMMUNITY EDUCATION CENTER LOWER LEVEL FIT-UP
 PORTLAND, MAINE
 CURRENT ISSUE STATUS:
ISSUED FOR PRICING/PERMITTING 4-18-06

REV	DESCRIPTION	DATE
0	ISSUED FOR PRICING/PERMITTING	4-18-06

GRAPHIC SCALE:
 0" 1"

SCALE: AS NOTED
 PROJECT MANAGER: SLB
 JC/DRAWN BY: TCM
 A/E OF RECORD: SLB
 CAD FILE: AD101-06004
 PROJECT NO: 06004
 DATE: 4-18-06

SHEET TITLE:
DEMOLITION PLAN

SHEET No.
AD101

A1 DEMOLITION PLAN

1/4" = 1'-0" *