



GENERAL NOTES:

1. RE: G1002 FOR GENERAL NOTES.

DEMOLITION PLAN NOTES:

1. REFER TO PLUMBING & MECHANICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS.
2. COORDINATE REMOVAL OF HARDWARE ON DOORS TO BE REUSED W/ DOOR SCHEDULE & HARDWARE SETS.
3. THE G.C. SHALL BE RESPONSIBLE FOR REPAIR AND REFINISH OF DAMAGED ITEMS NOT SCHEDULED TO BE DEMOLISHED.
4. ALL DIMENSIONS ARE TO FACE OF EXISTING FINISH, FACE OF MASONRY, CENTERLINE OF STUD PARTITIONS, & CENTERLINE OF DOORS & WINDOWS U.N.O.

DEMOLITION KEYNOTES:

- 1 REMOVE WALL (TYP. WHERE INDICATED BY DASHED LINES).
- 2 REMOVE COUNTERTOP AND CASEWORK.
- 3 REMOVE WINDOW(S). RETAIN FOR RE-USE WHERE INDICATED IN WINDOW SCHEDULE.
- 4 REMOVE DOOR(S). RETAIN FOR RE-USE WHERE INDICATED IN DOOR SCHEDULE.
- 5 REMOVE HOSE CABINET AND RETAIN FOR RE-USE IN NEW LOCATION.
- 6 REMOVE SECURITY GATE, FRAME AND HARDWARE.
- 7 REMOVE PORTION OF 2 HR SHAFTWALL ASSEMBLY TO FACILITATE ELEVATOR INSTALLATION.
- 8 REMOVE GWB CEILING.
- 9 REMOVE PORTION OF GWB CEILING.
- 10 REMOVE FLOOR TILE IN THIS AREA AND PATCH WITH FLOOR LEVELING COMPOUND.
- 11 REMOVE VCT (SEE ROOM FINISH SCHEDULE).
- 12 UNDER ALTERNATE #6, REMOVE PORTION OF WALL AS REQUIRED TO FACILITATE INSTALLATION OF NEW ELEVATOR.
- 13 UNDER BASE BID, COORDINATE DEMOLITION OF FLOOR SLAB AND FILL W/ REQUIREMENTS FOR ELEVATOR SUPPORTS PROVIDED BY ELEVATOR SUPPLIER. THE SAME APPLIES FOR ALTERNATE #6.
- 14 REMOVE EXISTING SLATE FLOORING & FLOOR URINAL.
- 15 EXTENT OF EXISTING CONCRETE EQUIPMENT PADS & NEW FLOOR TOPPING POURED DURING PREVIOUS RENOVATIONS. FIELD VERIFICATION OF SIZE & LOCATION IS REQUIRED.
- 16 REMOVE EXISTING WOODEN RAMP & HANDRAILS.
- 17 ROOF PENETRATION, COORDINATE LOCATION W/ STRUCTURAL & MECHANICAL DRAWINGS.
- 18 REMOVE PORTION OF EXIST. CONC. EQUIPMENT PAD TO ALLOW RECESS OF FLOOR TRACK FOR COMPACT MOVEABLE SHELVING SYSTEM. COORD. LOCATION & SIZE REQ. W/ SYSTEM SUPPLIER.
- 19 UNDER ALTERNATE #4 COORDINATE LOCATION OF PIPING PENETRATIONS WITH MECHANICAL & STRUCTURAL DRAWINGS.

REV.	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	3-17-03

ISSUED FOR CONSTRUCTION
3-17-03

CURRENT ISSUE STATUS:

SMRT ARCHITECTURE ENGINEERING PLANNING
 144 Fore Street P.O. Box 618
 Portland, Maine 04104
 tel. (207) 772-3846
 fax. (207) 772-1070

GLICKMAN LIBRARY
UNIVERSITY OF SOUTHERN MAINE
 PORTLAND, MAINE

PROJECT:
ROOF LEVEL DEMOLITION PLAN

SHEET TITLE:	SCALE: 1/8"=1'-0"	DATE: 3-17-03
PROJECT MANAGER: SLB	JOB CAP/DRAWN: CTB	GRAPHIC SCALE: 0" 1"
A/E OF RECORD: JLH	SMRT CAD FILE: AD108-99092	SHEET No.
PROJECT No. 99092		AD108