



F7	DETAIL ~ RO WATER PIPING SCHEMATIC
NOT TO SCALE	

D7	EXISTING PIPE RISER PHOTO
NOT TO SCALE	

PIPING KEYED NOTES:

1. ROS & R:
   PROVIDE ROS & RETURN PIPING AS PER DETAIL F7 - SHEET PL-100.
   a. PROVIDE 3/4" ROS BRANCH DROP DOWN IN CHASE/WALL TO PURE WATER FAUCET AT P-15 SINK
   b. LOOP THE 3/4" ROS PIPE BACK UP CHASE, CONTINUE THE ROS MAIN PER DETAIL.

2. NATURAL GAS (NG) & COMPRESSED AIR (CA):
   PROVIDE A 1/2" NG & CA DROP DOWN IN CHASE/WALL. ROUTE 1/2" NG & CA UNDER COUNTER TO EACH TURRET ON BENCH.

3. PROTECTED CW / NON-POTABLE WATER (PCW):
   PROVIDE A 1/2" PCW DROP DOWN IN CHASE
   a. ROUTE 1/2" PCW TO TWO FH-1 CUP SINK FAUCETS
      (SEE FUME HOOD KEYNOTE BELOW)
   b. ROUTE 1/2" PCW TO P-1 FAUCET
   c. ROUTE 1/2" PCW TO ADJACENT FLOOR DRAIN TRAP PRIMER (CORE HOLE IN FLOOR)

4. VACUUM (VAC):
   PROVIDE A 3/4" VAC DROP DOWN IN CHASE/WALL, ROUTE 1/2" VAC UNDER COUNTER TO EACH VAC TURRET ON BENCH.

5. PROVIDE 1" TW DROP TO ES-1 EMERGENCY SHOWER STATION. PROVIDE 1/2" PCW DROP TO FLOOR DRAIN TRAP PRIMER.

6. (E) VALVED/CAPPED PIPES AT 9'-0" AFF (+/-) - BOTTOM OF RO DRAIN AT 7'-0" AFF.

7. PROVIDE ½" CW DOWN IN WALL TO AUTOCLAVE. ROUTE 1" DRAIN TO FLOOR DRAIN LEAVING AN AIR GAP AS REQUIRED BY CODE.

Scale: 1/4" = 1'-0"

PLAN NORTH

A1	PLUMBING AND PROCESS PIPING PART PLAN
1/4" = 1'-0"	

A8	PLUMBING KEYED NOTES
NTS	

HKTA / architects
HKTA architects, inc.
462 Congress Street Suite 502
Portland, Maine 04101
phone: 207 . 774 . 6016
fax: 207 . 774 . 0126
email: hkta@maine.rr.com

Allied Engineering
Structural Mechanical
Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com

STATE OF MAINE
IAN A. MACDONALD
No. 8990
LICENSED
PROFESSIONAL ENGINEER

REVISIONS

NUMBER	DATE	BY	DESCRIPTION

Date: 3/28/2014
Drawn By: REW
Checked By: IAM
Project Mgr: IAM
Project No: 14003
Cad File: 140038M.dwg
Graphic Scale: 0 1"

PLUMBING AND PROCESS PIPING

UNIVERSITY OF SOUTHERN MAINE BIO-SCIENCE
~ 3rd FLOOR LAB FIT-UP
PORTLAND, MAINE

PL-100

N:\Projects\2014\14003 - USM Bio Science\00 Drawing Files\140038M.dwg Mar 27, 2014 - 8:32am