A WOOD 1/4" GLASS FACTORY FINISH

B WOOD 1/4" GLASS FACTORY FINISH

C WOOD FLUSH SLAB FACTORY FINISH

1 H.M.

2 H.M.

FG HOLLOW METAL

DOOR TYPES, FRAME TYPES

CONFIRM THROAT SIZES OF ALL METAL FRAMES TYP

0 4 8 12 16 FT

WINDOW TYPES

DOOR SCHEDULE

ID			Nominal Size			Location	Door Style			Glass	Door Frame					Fire Rating		Hdwr	Openings		Door Data	
Prefix	Mark	Suffix	Width	Height	Thickness		Door Operation	Door Matl	Door Type		Frame Matl	Frame Type	Head Detail	Jamb Detail	Sill Detail	Frame	Door Slab	HW Set See Spec	RO Width Nom.	RO Height Nom.	Accessories	Comments
3	80A	1	3'8"	7'0"	1 3/4"	C393	Swing Simple	WD	B	Safety	HM	2	2/A-401	1/A-401					4'0"	7'2"	KICK PLATE	
3	80A	2	3'0"	7'0"	1 3/4"	C300	Swing Simple	WD	EXST		HM	EXST	2/A-401	1/A-401					3'4"	7'2"		EXST DOOR IN CORR. C380A
3	92		3'0"	7'0"	1 3/4"	C393	Swing Simple	WD	C		HM	1	2/A-401	1/A-401					3'4"	7'2"		
3	93A		3'0"	7'0"	1 3/4"	C393A	Swing Simple	WD	A	Safety	HM	1	2/A-401	1/A-401					3'4"	7'2"	ARMOR PLATE	DOUBLE ACTING

WINDOW SCHEDULE

ID			Nominal Size		Location	Window Style			Glass	Frame Details			Code	Openings			Window Data	
Prefix	Mark	Suffix	Unit Width	Unit Height		Sash Operation	Frame Matl	Window Type		Head Detail	Jamb Detail	Sill Detail	Egress Window	RO Width	RO Height	Rough Sill Hgt	Accessories	Comments
3	93	A	2'10"	3'10"	C393	Fixed Glass	H.M.	FG	Safety					2'10"	3'10"	3'4"		

FINISH LEGEND

CEILING
ACT1 ACOUSTIC CEILING TILE
WALL
PGB PTD GYPSUM WALL BOARD
BASE
VB VINYL BASE - 4"
FLOOR
VCT VINYL COMPOSITION TILE

ROOM FINISH SCHEDULE

Room		Floor		Wall				Ceiling	Remarks
Number	Room Name	Matl	Base	North	East	South	West	Matl	
C393	BIOLOGY LAB	VCT	VB	PGB	PGB	PGB	PGB	ACT1	
C393A	CULTURE ROOM	VCT	VB	PGB	PGB	PGB	PGB	ACT1	

1 PARTITION TYPE 1
1 HR-RATED

2 PARTITION TYPE 2
NON-RATED

WALL TYPES

6 A-401 WALL CABINET
Scale: 1 1/2" = 1'-0"

7 A-401 OPEN CABINET
Scale: 1 1/2" = 1'-0"

8 A-401 COUNTER SINK
Scale: 1 1/2" = 1'-0"

2A A-401 DBL ACTING DOOR HEAD
Scale: 1 1/2" = 1'-0"

1A A-401 DBL ACTING DOOR JAMB
Scale: 1 1/2" = 1'-0"

2 A-401 INT DOOR HEAD
Scale: 1 1/2" = 1'-0"

1 A-401 INT DOOR JAMB
Scale: 1 1/2" = 1'-0"

3 A-401 SECTION @ WINDOW SILL & COMPUTER STATION
Scale: 1 1/2" = 1'-0"

4 A-401 DOOR/DRAWER CABINET
Scale: 1 1/2" = 1'-0"

5 A-401 MULTIPLE DRAWER CABINET
Scale: 1 1/2" = 1'-0"

NOTE:

USE AWI STANDARDS FOR ALL SHELF THICKNESSES AND APPROPRIATE CORE MATERIAL TYP.

PROVIDE SOLID WD BLOCKING BETW STUDS @ ALL CASEWORK REQUIRED TO BE FASTENED TO WALLS, CONTRACTOR SHALL COORDINATE MOUNTING LOCATIONS W/ CASEWORK PROVIDER.

10 A-401 SECTION THRU HARDWD BENCH
Scale: 1 1/2" = 1'-0"

0 1 2 3 4 FT

Date: **3/26/14**
File name: **USM 3rd Flr Bio-science lab.vwx**

HKTA architects, inc.
482 Congress Street Suite 502
Portland, Maine 04101
HKTA/architect
phone: 207. 774
fax: 207. 774. 91.
email: hkta@aol.com

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/19/14

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com

REGISTERED ARCHITECT ROBERT HOWE No. 1241 STATE OF MAINE

REVISIONS

NUMBER	DATE	BY	DESCRIPTION

Date: 3/28/2014
Drawn By: WGC
Checked By: REH
Project Mgr: IAM
Project No: 14003
Cad File: HKTA 2014001
Graphic Scale: 0 1"

DOORS, ARCH DETAILS, SCHEDULES THIRD FLOOR

UNIVERSITY OF SOUTHERN MAINE BIO-SCIENCE ~THIRD FLOOR LAB RENOVATION - BIOLOGY
PORTLAND, MAINE

© COPYRIGHT 2014 ALLIED ENGINEERING, INC.

A-401