J1	LEVEL 2 ELECTRICAL REMOVALS PLAN
1/4" = 1'-0"	

1 ABOVE CEILING RECEPTACLE AND VIDEO CONNECTIONS TO PROJECTOR ARE EXISTING TO REMAIN.

2 PROJECTOR CONTROL IS EXISTING TO REMAIN.

3 REMOVE EXISTING SURFACE NONMETALLIC RACEWAY AND RELOCATE TECHNOLOGY OUTLET WITH (2) VOICE AND (2) DATA INTO WIREMOLD BELOW WHITEBOARD ~ SEE DWG. E-100.

4 REMOVE RECEPTACLE. BOX AND WIRING TO BE REUSED- SEE DWG. E-100.

5 REMOVE EXISTING SURFACE NONMETALLIC RACEWAY AND RELOCATE VOICE AND DATA OUTLETS INTO WIREMOLD BELOW WHITEBOARD. SEE DWG. E-100.

6 SWITCHES SHALL BE REMOVED. BOX AND WIRING SHALL REMAIN.

7 REMOVE 3-GANG LOW-VOLTAGE JACKS. PROVIDE BLANK COVER FOR EXISTING BOX.

G11	KEYNOTES

ELECTRICAL REMOVALS NOTES

1. REFER TO FLOOR PLANS FOR SCOPE OF WORK AREA. REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR THE ADDITIONAL DEMOLITION SCOPE OF WORK.

2. COMPLETELY DEMOLISH ALL ELECTRICAL ITEMS WITHIN DEMOLITION AREA, UNLESS NOTED OR INDICATED OTHERWISE. DEMOLITION SHALL INCLUDE BUT NOT BE LIMITED TO WIRING DEVICES, OUTLET BOXES, PULL BOXES, LIGHTING FIXTURES AND SWITCHES, WIRING AND CONDUIT, TELECOMMUNICATIONS, ETC.

3. EXISTING ITEMS TO BE REMOVED ARE INDICATED FOR INFORMATIONAL PURPOSES, BUT THE DRAWINGS ARE NOT INTENDED TO INDICATE ALL ITEMS TO BE REMOVED.

4. EXISTING FIRE ALARM SYSTEM SHALL REMAIN, EXCEPT WHERE SYSTEM COMPONENTS ARE LOCATED IN WALLS TO BE REMOVED. WHERE WALLS ARE TO BE REMOVED, REMOVE AND RELOCATE EXISTING FIRE ALARM COMPONENTS AS INDICATED AND AS REQUIRED. EXISTING FIRE ALARM COMPONENTS ARE GENERALLY NOT SHOWN.

5. DISCONNECT AND REMOVE ALL WIRING FOR EQUIPMENT TO BE REMOVED BACK TO THE POINT OF CONNECTION. NOTHING SHALL BE ABANDONED IN PLACE.

6. VERIFY ALL EXISTING SOURCES OF POWER TO EQUIPMENT PRIOR TO FINAL REMOVAL.

7. COORDINATE ALL SHUTDOWN PROCEDURES WITH THE OWNER PRIOR TO DISCONNECTING ANY CIRCUITS.

8. PROVIDE BLANK COVER PLATES FOR REMOVED POWER AND COMMUNICATIONS OUTLETS IN EXISTING WALLS TO REMAIN.

9. WHERE DEMOLITION IMPACTS WIRING TO EXISTING ITEMS TO REMAIN, PROVIDE WIRING AND CONNECTIONS AS REQUIRED TO RE-FEED ITEMS TO REMAIN.

10. THE WORK INCLUDES DISPOSAL OF ALL REMOVED ELECTRICAL ITEMS INCLUDING BALLASTS AND LAMPS. LEGALLY DISPOSE OF ALL HAZARDOUS MATERIALS.

J11	ELECTRICAL REMOVALS NOTES

LAVALLEE BRENSINGER ARCHITECTS
Boston | Manchester | Portland
305 Commercial Street, Portland, ME 04101
603.622.5450
www.LBPA.com

Date: 05/10/16

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2268
F: 207.221.2266
Web: www.allied-eng.com

STATE OF MAINE
CATHERINE A. FAUCHER
No. 7575
LICENSED
PROFESSIONAL ENGINEER

University of Southern Maine

Science Building
Lab A203 Renovation

70 Falmouth Street
Portland, ME 04104

NO.	DESCRIPTION	DATE
	ISSUED FOR PERMIT	03/17/2016

N

CONTENT:
ELECTRICAL REMOVALS PLAN AND NOTES

DRAWN BY:	GMC
PROJECT NO:	16-005-00
DATE:	3/17/2016
REVISED:	
SCALE:	1/4" = 1'-0"

ED-100

Project Phase
BID DOCUMENTS

COPYRIGHT © 2015. BY LAVALLEE/BRENSINGER PROFESSIONAL ASSOCIATION. ALL RIGHTS RESERVED.
NO REPRODUCTION WITHOUT PERMISSION.

FOR ADDITIONAL INFORMATION, REFER TO PROJECT MANUAL.

N:\Projects\2016\16009 - USM Lab A203 Upgrade\1 Design\Phase\2 DRAWINGS\16009E.rvt
3/11/2016 2:20:53 PM