



SECTION 099123:

PAINING:

1. PROJECT INCLUDES SURFACE PREPARATION AND PAINT FOR INTERIOR SURFACES AS SCHEDULED. PROVIDE SURFACE PREPARATION, PRIMER & PAINT APPLICATION AS RECOMMENDED BY THE PRIMER & PAINT MANUFACTURER. PROVIDE COMPATIBLE, FIRST GRADE, LOW V.O.C., PROFESSIONAL LINE PRIMER AND FINISH PRODUCTS FROM EITHER BENJAMIN MOORE OR SHERWIN WILLIAMS. PROVIDE ONE PRIME COAT AND 2 FINISH COATS OF PAINT OR AS REQUIRED TO COVER OVER PREVIOUSLY PAINTED SURFACES. COLORS ARE TO BE SELECTED BY THE ARCHITECT FROM MANUFACTURER'S FULL RANGE.
2. PROVIDE PAINT AS FOLLOWS:
 - A. GYPSUM DRYWALL WALLS: 1 COAT LATEX PRIMER & SEALER (MPI# 50), 2 FINISH COATS LATEX (MPI #52-MPI GLOSS LEVEL 3 "EGGSHELL").
 - B. HOLLOW METAL FRAMES: 1 COAT CEMENTITIOUS PRIMER (MPI# 26), 2 FINISH COATS W.B. LIGHT INDUSTRIAL COATING (MPI# 153-MPI GLOSS LEVEL 5 "SEMI-GLOSS")
3. PREPARE ALL SUBSTRATES FOR PAINT APPLICATION PER THE PAINT MANUFACTURER'S RECOMMENDATIONS.

DRY-ERASE COATING (ALTERNATE NO. 2):

1. BASIS OF DESIGN PRODUCT: SHERWIN WILLIAMS DRY-ERASE COATING.
2. APPLY IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING



ISSUED FOR PERMITTING AND CONSTRUCTION
12-20-13
CURRENT ISSUE STATUS:

SCALE: NOT TO SCALE
PROJECT MANAGER: SLB
JC/DRAWN BY: MLE
A/E OF RECORD: SLB
CAD FILE: A-004-12014-02
PROJECT NO: 12014-02
DATE: 12-20-13

SHEET TITLE:
MATERIAL SPECIFICATIONS

SHEET No. **A-004**
© COPYRIGHT 2012 SMRT INC.

144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrting.com

**USM SCIENCE BUILDING C WING
CYBER SECURITY LAB FIT-UP
PROJECT 2013-007**
PORTLAND, MAINE

