TECHNICAL NOTES:

1. MAINTAIN EXISTING FLOW AND TAMPER SWITCHES AND OTHER SPRINKLER SYSTEM DEVICE CONNECTIONS.
2. DUCT SMOKE DETECTORS ARE NOTED DIAGRAMMATICALLY IN THIS SPACE. REPLACE EACH EXISTING DUCT SMOKE DETECTOR WITH A NEW DEVICE AND CONNECT TO NEW FIRE ALARM SYSTEM. CONTRACTOR SHALL FIELD VERIFY THE EXACT LOCATION OF EACH EXISTING DETECTOR. IF 120V POWER IS REQUIRED, CONNECT TO NEARBY RECEPTACLE CIRCUIT.
3. RELEASE OF EXISTING SMOKE HATCH SHALL BE INITIATED BY ADJACENT SMOKE DETECTOR ONLY.
4. PROVIDE DOOR CONTACT/POSITION SWITCH AT ROOF HATCH & CONNECT TO FIRE ALARM SYSTEM VIA A MONITOR MODULE. SYSTEM TO RECEIVE A SUPERVISORY SIGNAL WHEN ROOF HATCH IS IN THE OPEN POSITION.

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 7/29/2013

REV.	DESCRIPTION	DATE
--	--	--
--	--	--
--	--	--
0	CONSTRUCTION DOCUMENTS	05.10.13

CONSTRUCTION DOCUMENTS
05.10.13

CURRENT ISSUE STATUS:

MAG. NORTH
PROJECT NORTH

STATE OF MAINE — STEPHANIE J. LAPLANT — No. 10272 — LICENSED PROFESSIONAL ENGINEER
05.10.13

WBRC
ARCHITECTS• ENGINEERS
WWW.WBRCAE.COM
BANGOR, MAINE 207-947-4511
PORTLAND, MAINE 207-828-4511
SARASOTA, FLORIDA 941-556-0757

MASTERTON HALL FIRE ALARM UPGRADE

PROJECT: PORTLAND, MAINE

FOURTH FLOOR FIRE ALARM PLAN

SHEET TITLE:

WBRC CAD FILE: 3842.11 – FA104

PROJECT No. 3842.11

GRAPHIC SCALE: 0" 1"

SCALE: AS NOTED

PM: SJL

DRAWN BY: KRM

A/E OF RECORD: SJL

SHEET No. FA104

© COPYRIGHT 2013 WBRC

A1	FOURTH FLOOR FIRE ALARM PLAN
1/8" = 1'-0"	--

6/3/2013 10:09 AM I:\3801-3900\384210 USM FIRE ALARM SYSTEM UPGRADES\2 DESIGN\DWGS\BLDG\MASTERTON 6F035\MASTERSON HALL FIRE ALARM UPGRADE\SHEETS\3842.11-FA104 FOURTH FLOOR FIRE ALARM PLAN.DWG KYLE.MAHAR