DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	A B C	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
	4.7			1			20	2	1.3			6' UNDER COUNTER REFRIG.
BREAD OVEN		4.7		3	60		30	4		2.0		SANDWICH PRESS
			4.7	5				6			2.0	
BREAD OVEN CONTROL CIRCUIT	1.0			7	20		20	8	0.7			SOUP WARMER
KITCHEN HOOD EXHAUST/LIGHTS		1.0		9	20		20	10		0.7		SOUP WARMER
CASH REGISTER RECEPT			1.0	11	20		20	12			1.3	REFRIGERATED SALAD BAR
BREAD SLICER	0.8			13	20		30	14	1.8			EXPRESSO MACHINE
BLENDER STATION		1.0		15	20			16		1.8		
RECEPT CONDIMENT STATION			0.2	17	20		20	18			1.5	UNDER COUNTER REFRIG.
BLENDER STATION	1.0			19	20		20	20	1.0			CASH REGISTER RECEPT
COFFEE BREWER		2.9		21	40		20	22		0.2		COUNTER RECEPT
			2.9	23			20	24			0.2	COUNTER RECEPT
SODA DISPENSER	1.0			25	20			26				SPACE
COUNTER RECEPT		0.2		27	20			28				SPACE
REFRIGERATED MECHANDISER			1.5	29	20			30				SPACE
PENDANT LIGHTS	0.8			31	20			32				SPACE
SPARE				33	20			34				SPACE
SPARE				35	20			36				SPACE
SPACE				37				38				SPACE
SPACE				39				40				SPACE
SPACE				41				42				SPACE
SUB–TOTAL	9.3	9.8	10.3		NEUTRAL BUS / GROUND BUS				4.8	4.7	5.0	SUB–TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE	200 AMP BUS	TOTAL kVA A	14.1	PANEL NO.	KPP
MAIN LUGS ONLY	200 AMP LUGS	TOTAL kVA B	14.5		
MOUNTING: SURFACE		TOTAL kVA C	15.3	LOCATION	SERVERY
SC RATING: 10,000 AIC		TOTAL kVA	43.9		
NOTES:					

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	A B C	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
CASH REGISTER STATION	1.0			1	20		20	2	0.4			RECEPTS C3 STORE
REACH IN REFRIGERATOR		1.2		3	20		20	4		0.7		LIGHTING C3 STORE
REACH IN FREEZER			1.3	5	20		20	6				SPARE
	1.3			7			20	8				SPARE
REACH IN FREEZER		1.6		9	20		20	10				SPARE
REFRIGERATOR MERCHANISER			0.6	11	20		20	12				SPARE
SPACE				13				14				SPACE
SPACE				15				16				SPACE
SPACE				17				18				SPACE
SPACE				19				20				SPACE
SPACE				21				22				SPACE
SPACE				23				24				SPACE
SPACE				25				26				SPACE
SPACE				27				28				SPACE
SPACE				29				30				SPACE
SPACE				31				32				SPACE
SPACE				33				34				SPACE
SPACE				35				36				SPACE
SPACE				37				38				SPACE
SPACE				39				40				SPACE
SPACE				41				42				SPACE
SUB–TOTAL	2.3	2.8	1.9		NEUTRAL BUS / GROUND BUS				0.4	0.7	0.0	SUB–TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE	100 AMP BUS	TOTAL kVA A	2.7	PANEL NO.	PP1
MAIN LUGS ONLY	100 AMP LUGS	TOTAL kVA B	3.5		
MOUNTING: SURFACE		TOTAL kVA C	1.9	LOCATION	C3 STORE
SC RATING: 10,000 AIC		TOTAL kVA	8.4		
NOTES:					

LIGHT FIXTURE SCHEDULE

TYPE	DESCRIPTION	MFR.	LAMPS	MOUNTING	NOTES
A	BLEEKER STREET DECORATIVE PENDANT 120V	TBD BY ARCHITECT	TBD	PENDANT	
B	PURA VIDA DECORATIVE PENDANT 120V	TBD BY ARCHITECT	TBD	PENDANT	
C	EXISTING INDIRECT LINEAR FLUORESCENT 120V	EXIST. TO REMAIN	EXIST. TO REMAIN	AIR CRAFT CABLE	
D	EXISTING 2x4 RECESSED TROFFERS WITH ACRYLIC LENS. 120V	EXIST. TO BE RELOCATED	2–F32T8 3500K	CEILING RECESSED	
D	8" ROUND APERATURE DOWNLIGHT W/AMERICAN MATTE REFLECTOR. 120V	PRESCOLITE CFT832 SERIES	1–32W TRIPLE TUBE	CEILING RECESSED	
	THERMOPLASTIC EXIT SIGN W/WHITE FACE & RED LETTERING 120V	PRESCOLITE NV3 SERIES	LED	CEILING OR WALL	PROVIDE SINGLE OR DOUBLE FACE AS REQUIRED
	EMERGENCY LIGHTING UNIT W/ MAINT. FREE BATTERY & SELF TESTING ELECTRONICS 120V	PRESCOLITE NV SERIES	INTEGRAL WITH UNIT	SURFACE WALL	

E.S. BOULOS CO
ELECTRICAL CONTRACTORS
45 BRADLEY DRIVE
WESTBROOK, ME 04092
TEL: (207) 464–3706
FAX: (207) 464–1833

SMRT
ARCHITECTURE ENGINEERING PLANNING
SMRT
144 Fore Street / P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070

STATE OF MAINE
DANIEL J. TIBBETTS
NO. 9836
REGISTERED PROFESSIONAL ENGINEER
6/26/06

PROJECT TITLE:
UNIVERSITY OF MAINE
KITCHEN RENOVATIONS
PORTLAND & GORHAM CAMPUS

CURRENT ISSUE STATUS:
ISSUED FOR CONSTRUCTION
6-23-06

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	6-23-06

GRAPHIC SCALE: 0" 1"

SCALE:	AS NOTED
PROJECT MANAGER:	DJT
JC/DRAWN BY:	LAM
A/E OF RECORD:	DJT
CAD FILE:	E-601-06107
PROJECT NO:	06107
DATE:	6-23-06

SHEET TITLE:
ELECTRICAL SCHEDULES

SHEET No.
E-601

© COPYRIGHT 2005 SMRT INC.