



**SECTION VIEW - MODEL 4530 VH1-ND**

**SPECIFICATIONS: VH1-ND MODEL**

THE MODEL VH1-ND IS A SINGLE WALL TYPE HOOD WITH NO BUILT-IN MAKE-UP AIR CAPABILITIES.

THE HOOD COMPONENTS SHALL BE FABRICATED OF TYPE 304 S/STEEL, #3 OR #4 POLISH, ON ALL EXPOSED SURFACES.

THE HOOD SHALL BE PROVIDED WITH HANGING ANGLES ON EACH END OF THE HOOD.

THE HOOD SHALL BE FITTED WITH A 1" THICK REMOVABLE MESH FILTER AT EACH DUCT LOCATION. FILTERS SHALL BE EASILY REMOVABLE FOR CLEANING PURPOSES.

HOOD LIGHTS SHALL BE UL LISTED AND NSF LISTED FOR USE IN COMMERCIAL COOKING HOODS. EACH FIXTURE WILL ACCOMMODATE A 100 WATT INCANDESCENT BULB.

NOMINAL HOOD DIMENSIONS SHALL BE AS SHOWN ON DRAWINGS.

FOR QUESTIONS, CALL THE  
 EASTERN PA - DE - SOUTHERN NJ OFFICE  
 298 BLAIR MILL RD, STE 205, HORSHAM, PA 19044  
 PHONE: (215) 293-9665, (800) 323-3785  
 FAX: (215) 293-9669



<b>JOB</b>	Univ. of Maine - Oisen Center		
<b>LOCATION</b>	Farmington, ME		
<b>DATE</b>	6/22/2006	<b>JOB #</b>	
<b>DWG #</b>		<b>DRAWN BY</b>	DCN
<b>REV.</b>	1.00	<b>SCALE</b>	8.5" x 11"