DEMOLITION NOTES:

1.) ALL HAZARDOUS MATERIALS TO BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS.

2.) REMOVAL ALL UNUSED PLUMBING, ELECTRICAL, AND MECHANICAL ELEMENTS THAT ARE NOT PROPOSED TO BE REUSED

3.) REMOVE ALL CEILINGS AND STRAPPING TO JOISTS AS WELL AS ANY IN CEILING ELEMENTS SUCH AS INSULATION, ETC.

4.) IF ANY ELEMENTS TO BE REMOVED ARE FOUND TO BE STRUCTURAL, THE G.C. SHALL NOTIFY THE ARCHITECT IN WRITING PRIOR TO REMOVING SUCH ELEMENTS

5.) AT OFFICE WALLS, REMOVE ONE SIDE OF GWB FOR ADDITION OF SOUND BATTS

DEMOLITION LEGEND

WALL TO BE REMOVED

WALL STUDS AND SHEATHING TO REMAIN

WINDOW TO BE REMOVED

DOOR TO BE REMOVED

1 THIRD FLOOR DEMO PLAN
1/8" = 1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/11/15

RYAN J. SENATORE No. 3322 STATE OF MAINE

© 2015 RYAN SENATORE ARCHITECTURE

UNITED INSURANCE AGENCY
470 FOREST AVE.
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS ST.
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE:	MARCH 31, 2015
PROJECT No.	1446
DRAWN BY:	RRT / RJS
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:

THIRD FLOOR DEMO PLAN

AD1-3