Inspection Division
Date: 06/30/14

Reserved for City of Portland, Maine use

# FINISH SCHEDULE

NOTE:
- ALL FINISH ITEMS ARE FURNISHED BY GC, INSTALLED BY GC, UON
- NOT ALL ITEMS LISTED BELOW ARE USED ON THIS PROJECT
- REFER TO PLANS & DETAILS FOR LOCATION OF ITEMS USED ON THIS PROJECT
- ALL PAINT TO BE EGGSHELL FINISH, UON

| CODE | MATERIAL | MANUFACTURER | MODEL | COLOR | MODULE | MAIN CONTACT | REMARKS |
|---|---|---|---|---|---|---|---|
| ACP-1 | ACOUSTICAL CEILING PANEL | ARMSTRONG | DUNE 1775 | WHITE | 24"x24"x5/8" | PHILLIS MILLER 800-442-4212 | SUPRAFINE XL EXPOSED TEE |
| CPT-1 | CARPET TILE | BENTLEY PRINCE STREET | NEW DEMOGRAPHIC CUSTOM | CUSTOM COLOR | 24"x24" | CHRIS CLARK 330-391-4614 | INSTALL QUARTER TURNED |
| CPT-2 | WALK-OFF MAT | BENTLEY PRINCE STREET | DECO RIB 6230100004 | ANTIRACITE 602371 | 19.69"x19.69" | DONNA DAVIS 908-849-3076 | VESTIBULE, INSTALL QUARTER TURNED |
| CPT-3 | CARPET TILE | BENTLEY PRINCE STREET | 8MK28-0220T MODERN BLOK | CRUSHED STONE - 801081 | 24"x24" | CHRIS CLARK 330-391-4614 | INNOVATION ZONE, INSTALL QUARTER TURNED |
| FRP-1 | FIBER REINFORCED PLASTIC BOARD | MARLITE | S100G | WHITE | 4'-0"X8'-0" | MARLITE 330-343-6621 | JANITOR, LOUNGE WALL BY LADDER |
| G-1 | GROUT TEC | ACCUCOLOR | XT SANDED | CORNSILK #906 | 1/8" GROUT JOINTS | TEC www.tecspecialty.com | USE WITH RF-2 TILE |
| PL-1 | PLASTIC LAMINATE | NEVAMAR | RK 2001-T | CLASSIC ROCK | --- | NEVAMAR www.nevamar.com | TELLER LINE FRONT |
| PL-2 | PLASTIC LAMINATE | WILSONART LAMINATE | 11046K-07 | MOCHA CHERRY | --- | WILSONART www.wilsonart.com | BACK OF HOUSE CABINET FRONTS |
| PL-3 | PLASTIC LAMINATE | NEVAMAR | RK 2001-T | CLASSIC ROCK | --- | NEVAMAR www.nevamar.com | BACK OF HOUSE COUNTER TOPS |
| PL-4 | PLASTIC LAMINATE | WILSONART LAMINATE | 11046K-07 | MOCHA CHERRY | --- | WILSONART www.wilsonart.com | INNOVATION ZONE TABLES & TELLER LINE |
| PT-1 | PAINT | SHERWIN WILLIAMS | PRO MAR ZERO VOC EG-SHELL, B20-600 | ACCESSIBLE BEIGE SW7036 | --- | RYAN SCHNEEMAN 216-566-1765 | ALL INTERIOR WALLS, UON EXTRA WHITE BASE |
| PT-2 | PAINT | SHERWIN WILLIAMS | PRO MAR ZERO VOC EG-SHELL, B20-600 | TURKISH COFFEE SW6076 | --- | RYAN SCHNEEMAN 216-566-1765 | ALL INTERIOR WALLS, UON EXTRA WHITE BASE |
| PT-3 | PAINT | SHERWIN WILLIAMS | PRO MAR ZERO VOC FLAT, B30-600 | CITYSCAPE SW7067 | --- | RYAN SCHNEEMAN 216-566-1765 | ACCENT PAINT OFFICE WALL & CONFERENCE ROOM |
| PT-4 | PAINT | SHERWIN WILLIAMS | DURATION HOME SATIN | RAVE RED SW6608 | --- | RYAN SCHNEEMAN 216-566-1765 | TELLERLINE PORTAL CEILING, LEVEL 5 FINISH |
| PT-5 | PAINT | SHERWIN WILLIAMS | BRILLIANT WHITE | WHITE | --- | 877-397-7897 www.flamestop.com | CEILING PAINTING |
| PT-6 | PAINT | SHERWIN WILLIAMS | PRO CLASSIC WATER BOUNCE SEMI-GLOSS | IRON ORE SW 7069 | --- | RYAN SCHNEEMAN 216-566-1765 | METAL DOORS & FRAMES |
| RB-1 | RUBBER BASE | JOHNSONITE | COVE BASE | FUDGE | 4" HEIGHT | LAURIE BAATZ 440-313-8238 | |
| RF-1 | VCT | ARMSTRONG | IMPERIAL TEXTURE STANDARD EXCELON | WASHED LINEN - 51810 | 12"X12" | TRINA SIEGRIST 717 3963676 | BACK OF HOUSE LOUNGE, ETO, ATM, ELECT, |
| RF-2 | PORCELAIN TILES | CROSSVIUE | SAHARA DUNE | A235 SAHARA DUNE | 3"x3" | SHEILAH WINN 8656750939 | RESTROOMS PROVIDE INTEGRAL COVE BASE, INSIDE OUTSIDE CORNERS & BULL NOSE EDGES |
| RS-1 | REDUCER STRIP | CERAMIC TOOL CO. | CTC38CT | ALUMINUM-CLEAR ANODIZED | --- | --- | |
| RS-2 | REDUCER STRIP | JOHNSONITE | CTA-XX-D | FUDGE | --- | --- | |
| RS-3 | REDUCER STRIP | JOHNSONITE | CTA-XX-H | FUDGE | --- | --- | |
| RS-4 | REDUCER STRIP | JOHNSONITE | EG-XX-G | FUDGE | --- | --- | |
| RS-5 | REDUCER STRIP | JOHNSONITE | CTA-XX-K | FUDGE | --- | --- | |
| RS-6 | REDUCER STRIP | CERAMIC TOOL CO. | CTC38CTB | ALUMINUM-CLEAR ANODIZED | --- | --- | |
| T-1 | VINYL TILE | MANNINGTON | SPATIA | EBONY WOOD SS5W2511 | 7 1/4"X48" | --- | LOBBY-FIELD |
| T-2 | VINYL TILE | MANNINGTON | SPATIA | WHITE ASH SS5W2540 | 7 1/4"X48" | --- | LOBBY-ACCENT |
| ST-1 | STAIN | --- | --- | MATCH KIMBALL WOOD FURNITURE FINISH | --- | --- | GC TO VERIFY WITH MILLWORK VENDOR |
| WT-1 | WINDOW BLINDS | MECHOSHADE | MECHOSHADE 5 WITH METAL CHROME PULL CHAIN | STONE 6018 | --- | | INCLUDE OPTIONAL FASCIA; COLOR: ALUMINUM |
| WT-2 | WINDOW FILM | 3M | FASARA | OPAQUE WHITE | --- | --- | |
| SS-1 | SOLID SURFACE | -- | | DELTA SAND | | | TELLER COUNTER TOP AND FRONT PANEL |
| WC-1 | WALL COVERING | SURFACE MATERIALS | SANFOOT | NATURAL WOOD VENEER WALLCOVERING QC FIGURED ANIGRE | 3'-9"X3'10" | MICHELLE VNUK | INNOVATION MEDIA WALL |
| ACP-2 | ACOUSTICAL CEILING PANEL | ARMSTRONG | 12" AXIOM TRIM | WHITE | 12"X3/4" | PHILLIS MILLER 800-442-4212 | INNOVATION ZONE CLOUD TRIM CHANNEL |
| 4" CAN | 4" CAN LIGHT | GOTHAM | EVO-356 4AR 120 | - | 4" DIA. | - | VARIES |
| 2X2 | 2X2 STANDARD LIGHT | LITHONIA | 2RT5-24T5HO-MVOLT-GEB10PS-LP835 | - | 2x2 | - | STANDARD 2x2 BRANCH FIXTURE |

STYLE: CARPET TRIM (JOHNSONITE #CTA-XX-D) | STYLE: CARPET TRIM (JOHNSONITE #CTA-XX-K) | STYLE: CARPET TRIM #CTC38CTB

## FINISH PLAN KEY NOTES:

1. ALL LIGHT WOOD DOORS, FRAMES AND TRIM TO BE REFINISHED IN PT-2, TURKISH COFFEE. TYP. ENTIRE BRANCH
2. EXIST'G WOOD BASEBOARD TO BE CLEANED AND REFINISHED IN PT-2, TURKISH COFFEE. TYP OF ENTIRE BRANCH
3. CLEAN AND REPAIR ANY TILE AND GROUT AS NEEDED. TYP OF ENTIRE BRANCH
4. PATCH AND INFILL CARPET AS NEEDED FROM NEW TELLERLINE INSTALL
5. EXIST'G BLOCK 'O' CEILING SOFFIT TO BE PAINTED ALL IN PT-5
6. SOFFIT ABOVE TELLERLINE TO BE PAINTED PT-4

## SYMBOL LEGEND

- INDICATES AREA NOT IN SCOPE OF WORK
- FLOORING TRANSITION STRIP: REFER TO GENERAL FINISH NOTES FOR SPECIFICATION INFORMATION AND DETAILS
- DENOTES DIRECTION OF FLOORING INSTALLATION.
- XXX WALLS
- XXX FLOORS
- XXX BASE

**ADD ALTERNATE:**
GC TO PROVIDE SEPARATE LINE ITEM COST FOR THE FOLLOWING EXTERIOR WORK:
- SCRAPE, REPAIR AND PAINT ALL EXTERIOR TRIM. COLOR SPECIFIED BY KEYBANK. TYP. ENTIRE BUILDING
- PATCH, REPAIR AND PAINT ALL EXTERIOR EIFS. COLOR SPECIFIED BY KEYBANK. TYP. ENTIRE BUILDING

**NOTE:**
EXISTING CARPET MAY BE 18"X18" TILES INSTEAD OF STANDARD 24"X24" TILES. GC TO WORK WITH KEYBANK TO FIND ATTIC STOCK OR REPURPOSE TILES FROM OTHER ROOMS. ALL PATCHED AREAS ARE TO USE FULL TILES. GC IS RESPONSIBLE FOR INCLUDING IN HIS ORIGINAL COST.

GRADE LEVEL
1 FINISH PLAN
SCALE: 1/4" = 1'-0"

Project North


vocon.
cleveland.
3142 Prospect Ave.
Cleveland OH, 44115
216.588.0800
new york.
Two Grand Central Tower, Suite 14A.
140 East 45th Street
New York, NY 10017
646.865.1200
vocon. partners LLC.


I hereby certify that this drawing, Specification, plan, or report was prepared by me or under my direct supervision and that I am a duly registered Architect (or Engineer, respectively) under the laws of the State of which govern this project. WARNING: per LAW No person may alter these documents unless person is " or under the direct supervision of " the licensed record architect (or Engineer, respectively). [ inclouding all copyrights: JCW ]
PROFESSIONAL SEAL:

Date: _____
*John C. Workley* Registration No: 03-62844-1
Expiration Date: 6/30/2015

PROPOSED TENANT IMPROVEMENTS FOR:

**KeyBank National Association**
Forest Avenue Branch
400 Forest Ave.
Portland, Maine 04101

DRAWING RELEASE

| No. | Date | Description |
|---|---|---|
| 1 | 05/28/2014 | OWNER REVIEW |

DRAWN BY: SDR
CHECKED BY: SDW
JOB NUMBER: 140480.00

DATE ISSUED FOR: x/x/2014 - CD APPROVAL

SHEET TITLE:
FINISH PLAN, SCHEDULE AND NOTES

SHEET NUMBER:
A4.1

© 2014 vocon partners, llc.