



**NOTES:**  
 DOUBLE-FACE, INTERNALLY-ILLUMINATED, FABRICATED ALUMINUM POLE SIGN.  
 KEY TO BE CUT OUT OF ALUMINUM FACES; OPENING TO BE BACKED UP WITH WHITE #2447 PLEXIGLAS WITH FIRST SURFACE APPLIED 3M RED TRANSLUCENT VINYL TO MATCH PMS #1795C.  
 "KEYBANK" TO BE CUT OUT OF ALUMINUM FACES; OPENINGS TO BE BACKED UP WITH WHITE #2447 PLEXIGLAS WITH FIRST SURFACE APPLIED 3M BLACK PERFORATED DUO-FILM.  
 UPPER FACE BACKGROUNDS AND CABINET TO BE PAINTED MATTHEWS ACRYLIC POLYURETHANE SATIN HI-HIDE SPECIALTY WHITE #6425 SP.  
 LOWER FACE BACKGROUND AND CABINET TO BE PAINTED RED TO MATCH PMS #1795C.  
 POLE COVER TO BE PAINTED MATTHEWS ACRYLIC POLYURETHANE SATIN BLACK #N 923 SP.

RATED 120 VOLTS

ILLUMINATION TO BE PROVIDED BY CWHO FLUORESCENT LAMPS POWERED BY ELECTRONIC BALLASTS. SIGN TO BE BUILT TO U.L. SPECS, BE U.L. LISTED, AND CARRY U.L. LABEL.

P49

NOTE: due to printer limitations, colors shown may not exactly match specified. Refer to material charts for true colors.



# Brilliant Electric Sign Co., Ltd.

4811 VAN EPPS RD., CLEVELAND, OHIO 44131 (216)741-3800

NOTE: THIS IS AN ORIGINAL UNPUBLISHED DRAWING, CREATED BY BRILLIANT SIGNS. IT IS SUBMITTED FOR YOUR PERSONAL USE, IN CONJUNCTION WITH A PROJECT BEING PLANNED FOR YOU. IT IS NOT TO BE USED, REPRODUCED, COPIED OR EXHIBITED IN ANY FASHION.

COMPANY NAME <b>KeyBank</b>	SALESMAN <b>H</b>	DATE <b>4-30-14</b>	REVISION	DESIGN NO. <b>B14-1048</b>
LOCATION <b>400 Forest Avenue, Portland, Maine</b>	DESIGNER <b>DM</b>	SCALE <b>3/8" = 1'-0"</b>		COPYRIGHT © <b>2014</b>
FILE NAME <b>I:/Key 2014 CUI/maine/400 forest portland</b>				