CONSTRUCTION PLAN
SCALE: 1/4"=1'-0"

CONSTRUCTION PLAN
SCALE: 1/4"=1'-0"

1

KEY NOTES

1. NEW ADA COMPLIANT RAMP. REFER TO CIVIL ENGINEERING DWGS.
2. NEW 36" DOOR, DOOR FRAME, AND ASSOCIATED HARDWARE.
3. NEW COMPLIANT VESTIBULE CHECK DESK. SEE 1/A12.00.
4. NEW STOREFRONT SYSTEM TO MATCH EXISTING 'SLOPPED' INSTALATION.
5. NEW ADA COMPLIANT NCR PERSONAS 86 WALK UP THROUGH WALL ATM PROVIDED BY OWNER AND INSTALLED BY GC. INSTALL PER OWNERS STANDARDS AND MANUFACTURER INSTRUCTIONS , PROVIDE NECESSARY POWER AND COMMUNICATION CONNECTION.
6. NEW PARTITION TO MATCH EXISTING FINISHES.
7. NEW STOREFRONT SYSTEM TO MATCH EXISTING FINISHES.
8. NEW KNEE WALL TO SUPPORT STOREFRONT ABOVE. REFER TO STRUCTURAL ENGINEERING DRAWINGS.
9. FINISH FACE OF KNEE WALL TO MATCH EXISTING.
10. PROVIDE NEW MILLWORK COUNTER.

FINISH SCHEDULE

ITEM	PRODUCT (SEE CONTRACTOR NOTES AT BOTTOM OF PAGE)
CERAMIC TILE	DALTILE CONTACT: EMAIL: NATIONAL_ACCOUNT@DALTILE.COM; TOLL FREE NUMBER: 877.556.5728; FAX 214.309.4228
CT-1	FIELD TILE: 13" X 20" DALTILE: VERANDA 3/8" THICK TILE SAND P505 - SKUIPS0513201P GROUT (G-1): STARQUARTZ QUARTZLOCK2 255 SOLID BUFF - SKUIR9999630741
CT-2	ACCENT TILE: 5" X 20" DAL TILE: VERANDA 3/8" THICK TILE GRAVEL P501 - SKUIIPS0513201P1 GROUT (G-1): STARQUARTZ QUARTZLOCK2 255 SOLID BUFF - SKUIR9999630741
CT-3	ACCENT TILE: 13" X 20" DAL TILE: VERANDA 3/8" THICK TILE SUEDE P524 - SKUIIPS2413201P GROUT (G-2): STARQUARTZ QUARTZLOCK2 290 CHESTNUT - SKUIR9999630756
VINYL COMPOSITION TILE	
VCT-1	VINYL COMPOSITION TILE: 12" X 12" ARMSTRONG: 219 TOFFEE
WALK-OFF MAT	
WM-1	REESE PERFEC MAT/RUBBER HINGE/ TREAD RAILS: ANODIZED ALUMINUM, CLEAR/ POLYPROPYLENE BRUSH, GRAY/SQUARE VINYL EDGE, BLACK
WALL BASE	
B-2	JOHNSONITE FLEXIBLE WALL BASE, RUBBER, 4 1/2"X 3/8", #283 TOAST.
B-4A	JOHNSONITE FLEXIBLE WALL BASE, RUBBER, 4 1/2"X 3/8", #68 WHITE SAND.
CEILING	
ACT-1	ARMSTRONG; 24"X24" WHITE INTERIOR CEILING PANELS ; ASTM E 1264 TYPE 3 FORM 2 PATTERN CE.
PAINT	
P-1	BENJAMIN MOORE; ECO SPEC WB INTERIOR LATEX EGGSHELL ENAMEL NO. OC-122; COLOR: COTTON BALLS
P-2	BENJAMIN MOORE; ECO SPEC WB INTERIOR LATEX SEMI-GLOSS ENAMEL NO. 0C-122 COLOR: COTTON BALLS

SHEET NOTES

1. REFER TO A00.00 FOR GENERAL NOTES.
3. ALL NEW PARTITIONS TO BE PAINTED P-1 UON.
4. FURNITURE AND EQUIPMENT LOCATIONS ARE SHOWN FOR INFORMATION ONLY.
5. GC SHALL PROVIDE ALL WORK RELATED TO ENGINEERING TO INCLUDE, BUT NOT LIMITED TO: STRUCTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION & LIFE SAFETY, G.C SHALL PROVIDE DESIGN DRAWINGS, PERMITS & INSTALLATION OF SYSTEMS ON A DESIGN BUILD BASIS.
6. GC IS TO INSTALL THE ELECTRIFIED HARDWARE AND TO PROVIDE THE WIRING AND CONCEALED CONDUIT TO ATM SERVICE ROOM FOR TERMINATION BY OTHERS

	EXIT SIGN
F	FIRE ALARM STROBE
FA	FIRE ALARM PULL
FW	FIRE WARDEN STATION
	WALL MOUNTED, SINGLE RECEPTACLE
	WALL MOUNTED, DUPLEX RECEPTACLE
	WALL MOUNTED, QUADRAPLEX RECEPTACLE
	WALL MOUNTED, VOICE/DATA RECEPTACLE
	WALL MOUNTED, DATA RECEPTACLE
	WALL MOUNTED, VOICE RECEPTACLE
J	WALL MOUNTED, ELECTRICAL JUNCTION BOX
J	ABOVE CEILING SINGLE GANG J-BOX WITH 1/2" STUB UP.
CR	CARD READER

Bank of Amer
ATM Installation

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/13/15

500 Forest Avenue
Portland, ME 04101

Gensler

One Beacon Street
3rd Floor
Boston, MA 02108
Telephone 617.619.5700
Facsimile 617.619.5701

△	Issue	Date & Issue Description	By	Check
	1	06/03/2015	DG/CV	JR
		ISSUED FOR BID AND PERMIT		

Seal/Signature

LICENSED ARCHITECT
KENNETH I. FISHER
No. 3181
STATE OF MAINE

Project Name
BANK OF AMERICA
ATM INSTALLATION

Project Number
11.6563.084

CAD File Name
A02-01

Description
CONSTRUCTION PLAN

Scale
0 2' 4' 8' 16'

A02.01

©2015 Gensler