DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4"=1'-0"

REFLECTED CEILING PLAN
SCALE: 1/4"=1'-0"

1

KEY NOTES

1. REMOVE EXISTING CEILING TILES AND LIGHTING.
2. NEW GYPSUM BOARD CEILING TO BE INSTALLED AT EXISTING CEILING HEIGHT, U.O.N.
3. NEW CEILING GRID/ TILES AND LIGHTING. CEILING TO BE INSTALLED AT EXISTING CEILING HEIGHT U.O.N.
4. NEW (12" X 12") CEILING DIFFUSER; TITUS OMNI SERIES, WHITE (#26). SHOWN FOR REFERENCE ONLY. CONTRACTOR TO COORDINATE SIZE, LOCATION AND QUANTITY WITH DESIGN BUILD ENGINEER.
5. NEW (24" X 24") CEILING SUPPLY; TITUS OMNI SERIES, WHITE (#26). SHOWN FOR REFERENCE ONLY. CONTRACTOR TO COORDINATE SIZE, LOCATION AND QUANTITY WITH DESIGN BUILD ENGINEER.
6. PROVIDE CREE TYPE B 6" RECESSED DOWNLIGHT WITH WHITE TRIM.
7. PROVIDE 2' X 4' TYPE E LAMPS.
8. PROVIDE CREE TYPE IE 6" RECESSED DOWNLIGHT WITH WHITE TRIM.
9. SPRINKLER HEADS SHOWN FOR LOCATION ONLY. G.C. TO VERIFY COVERAGE AND PERFORMANCE OF EXISTING FIRE PROTECTION SYSTEM WITH DESIGN BUILD ENGINEER.
10. MATCH EXISTING CEILING FINISH AND HEIGHT.

SHEET NOTES

1. REFER TO A00.00 FOR GENERAL NOTES.
3. ALL NEW PARTITIONS TO BE PAINTED P-1 UON.
4. FURNITURE AND EQUIPMENT LOCATIONS ARE SHOWN FOR INFORMATION ONLY.
5. GC SHALL PROVIDE ALL WORK RELATED TO ENGINEERING TO INCLUDE, BUT NOT LIMITED TO: STRUCTURAL,MECHANICAL, ELECTRICAL, FIRE PROTECTION & LIFE SAFETY, G.C SHALL PROVIDE DESIGN DRAWINGS, PERMITS & INSTALLATION OF SYSTEMS ON A DESIGN BUILD BASIS.
6. GC IS TO INSTALL THE ELECTRIFIED HARDWARE AND TO PROVIDE THE WIRING AND CONCEALED CONDUIT TO ATM SERVICE ROOM FOR TERMINATION BY OTHERS

	EXIT SIGN
F	FIRE ALARM STROBE
FA	FIRE ALARM PULL
FW	FIRE WARDEN STATION
	WALL MOUNTED, SINGLE RECEPTACLE
	WALL MOUNTED, DUPLEX RECEPTACLE
	WALL MOUNTED, QUADRAPLEX RECEPTACLE
	WALL MOUNTED, VOICE/DATA RECEPTACLE
	WALL MOUNTED, DATA RECEPTACLE
	WALL MOUNTED, VOICE RECEPTACLE
J	WALL MOUNTED, ELECTRICAL JUNCTION BOX
CR	CARD READER

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/13/15

Bank of Amer
ATM Installation

500 Forest Avenue
Portland, ME 04101

Gensler

One Beacon Street
3rd Floor
Boston, MA 02108
Telephone 617.619.5700
Facsimile 617.619.5701

Issue	Date & Issue Description	By	Check
1	06/03/2015	DG/CV	JR
	ISSUED FOR BID AND PERMIT		

Seal/Signature

LICENSED ARCHITECT
KENNETH I. FISHER
No. 3181
STATE OF MAINE

Project Name
BANK OF AMERICA
ATM INSTALLATION

Project Number
11.6563.084

CAD File Name
A02-01

Description
CONSTRUCTION PLAN

Scale
0 2' 4' 8' 16'

A04.01

©2015 Gensler