

- (A) 6" x 6" PT, mounted to Piers w/ std 6x6 Galvanized clips
- (B) 2" x 12" PT (double plate, fastened with 3" #9 GRK Screws)
- (C) 2" x 4" KD 16" OC beneath Windows, fastened with 3" GRK #9 Screws
- (D) 2" x 8 1/2" x 8 1/2" Hollow Columns, each fastened 3/4 4" #10 GRK Screws into existing header
- (E) 3' x 12" Concrete Piers

26 Orlando st, Smith-Perkins Porch

Framing Schedule 2° Deck + Porch

Front View

