Inspections Division
Date: 11/02/15

NATHAN R. MERRILL, P.E.
171 ATWOOD ROAD
NEW GLOUCESTER, ME
207-299-2248
nathanmerrillpe@gmail.com

Project DUNWORTH RES - PORTLAND, ME
W.O. _____ Sheet 1.3 of 4
Calculated by _____ Date _____
Checked by _____ Date _____

STATE OF MAINE
NATHAN R. MERRILL
No. 12279
LICENSED PROFESSIONAL ENGINEER
9-11-15

TIMBER NOTES

1. ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH THE AITC TIMBER CONSTRUCTION MANUAL–LATEST EDITION, AND THE AF & PA NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS) LATEST EDITION.

2. INDIVIDUAL TIMBER FRAMING MEMBERS SHALL BE VISUALLY GRADED. MINIMUM GRADE NO1/NO2 SPRUCE–PINE–FIR KILN DRIED TO 19% MAXIMUM MOISTURE CONTENT UNLESS OTHERWISE INDICATED ON THE DRAWINGS.

3. ENGINEERED WOOD PRODUCTS SHALL BE AS SPECIFIED ON THE DRAWINGS. REFER TO MANUFACTURER'S LITERATURE FOR PROPER HANDLING AND INSTALLATION GUIDELINES. MANUFACTURER AND PRODUCT SHALL BE:

   TRUS–JOIST: I–JOIST (TJI), PARALLAM (PSL), MICROLAM (LVL), TIMBERSTRAND (LSL)
   BOISE: I–JOIST (BCI), VERSALAM (LVL)

4. SUBSTITUTIONS OF ENGINEERED WOOD MATERIALS OTHER THAN THOSE SPECIFIED WILL BE PERMITTED ONLY WITH WRITTEN CERTIFICATION FROM THE MANUFACTURER THAT SUBSTITUTED ITEMS "MEETS OR EXCEED" ALL PROPERTIES OF SPECIFIED PRODUCT, INCLUDING ENGINEERING AND DURABILITY CHARACTERISTICS. SUBSTITUTIONS ARE SUBJECT TO APPROVAL BY THE ARCHITECT AND ENGINEER.

5. PRESSURE TREATED LUMBER SHALL BE USED FOR SILL MEMBERS, EXTERIOR EXPOSURE, OR WHERE SHOWN ON THE DRAWINGS. TIMBER SHALL BE SOUTHERN YELLOW PINE TREATED WITH CCA OR ACQ TO 0.4 #/CF IN ACCORDANCE WITH AWPA C–18. ACZA IS STRICTLY PROHIBITED.

6. ALL ROOF AND WALL SHEATHING SHALL BE APA PERFORMANCE–RATED. PROVIDE 5/8" THICK CD–X ROOF SHEATHING AND 1/2" THICK WALL SHEATHING (U.N.O.) SEE SHEARWALL SCHEDULE FOR NAILING REQUIREMENTS EXCLUSIVE TO SHEARWALLS. SHEATHING SHALL BE NAILED TO THE FRAMING AS FOLLOWS, U.N.O.:

   TYPICAL PANEL FASTENING (U.N.O.)
   A. ROOFS: 8d NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES AND 12"O.C. AT INTERMEDIATE SUPPORTS.
   B. WALLS: 8d NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS.

7. FLOOR SHEATHING SHALL BE 3/4", APA RATED TONGUE AND GROOVE PANELS. GLUE AND NAIL TO FLOOR FRAMING WITH 8d RING SHANK NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS.

8. ALL BUILT–UP BEAMS AND COLUMNS SHALL BE NAILED AS FOLLOWS (FASTENING IN EACH PLY):

   UNIFORMLY LOADED BEAMS:
   BEAM DEPTH <16" – 2 ROWS OF 16d NAILS AT 12" O.C., STAGGERED
   BEAM DEPTH >=16" – 3 ROWS OF 16d NAILS AT 12" O.C. STAGGERED
   NOTE: SIDE LOADED BEAMS REQUIRE ADDITIONAL FASTENING. SEE DETAILS.

   COLUMNS:
   2–10d NAILS AT 6" O.C.

9. FASTENING NOT SPECIFIED SHALL CONFORM WITH IBC (2009) TABLE 2304.9.1. NAIL FASTENERS SHALL MEET THE REQUIREMENTS OF ASTM F1667. UNLESS NOTED OTHERWISE, NAILS REFERENCED ON DRAWINGS ARE TO BE COMMON NAILS WITH DIMENSIONS AS FOLLOWS.

   6d: 2" LONG BY 0.113" DIAMETER SHANK WITH 0.266" DIAMETER HEAD
   8d: 2 1/2" LONG BY 0.131" DIAMETER SHANK WITH 0.281" DIAMETER HEAD
   10d: 3" LONG BY 0.148" DIAMETER SHANK WITH 0.312" DIAMETER HEAD
   12d: 3 1/4" LONG BY 0.148" DIAMETER SHANK WITH 0.312" DIAMETER HEAD
   16d: 3 1/2" LONG BY 0.162" DIAMETER SHANK WITH 0.344" DIAMETER HEAD
   20d: 4" LONG BY 0.192" DIAMETER SHANK WITH 0.406" DIAMETER HEAD
   30d: 4 1/2" LONG BY 0.207" DIAMETER SHANK WITH 0.438" DIAMETER HEAD

10. ALL TIMBER CONNECTION HARDWARE (JOIST HANGERS, POST BASES, SHEARWALL HOLDOWNS, ETC) SHALL BE AS INDICATED ON THE DRAWINGS AND MANUFACTURED BY SIMPSON STRONG–TIE. ALL CONNECTION HARDWARE SHALL BE HOT–DIPPED GALVANIZED G–90 (U.N.O.). CONNECTION HARDWARE USED IN CONTACT WITH PRESERVATIVE TREATMENT SHALL BE GALVANIZED G185 (ZMAX) USE FASTENERS AND HANGERS OF SAME MATERIAL & COATING. REFER TO MANUFACTURER'S LITERATURE FOR PROPER HANDLING AND INSTALLATION GUIDELINES.

11. FASTENERS USED IN CONTACT WITH PT LUMBER SHALL BE HOT DIPPED GALVANIZED (ASTM A153), STAINLESS STEEL, OR OTHER FINISH AS APPROVED BY THE ENGINEER.